




ROOF FRAMING PLAN

1/8" = 1'-0"

- ROOF FRAMING PLAN NOTES:
- SEE STRUCTURAL NOTES ON SHEET 50.0.
 - COORDINATE ALL DIMENSIONS WITH ARCHITECTURAL DRAWINGS AND LIST CONDITIONS.
 - SEE PLANS FOR TOP OF STEEL BEAM / ROOF DECK BEARING ELEVATIONS AT GRIDLINES.
A. SLOPE STRUCTURAL STEEL FRAMING UNIFORMLY BETWEEN ELEVATIONS GIVEN AT GRIDLINES.
B. MEMBERS INDICATED AS [H- X-X'] AFTER THE BEAM MARK DESIGNATES A DIFFERENTIAL TOP OF STEEL ELEVATION FROM THE DECK BEARING. OR MEMBERS ARE NOTED THUS: [T.O.S. = X'-X']
 - (B) : INDICATES SPAN DIRECTION OF 3'-18ga. PRIME-PAINTED VULCRAFT 3" ROOF DECK.

(C) : INDICATES SPAN DIRECTION OF 3" CONCRETE SLAB ON 3'-18ga. VULCRAFT 3" GALVANIZED COMPOSITE METAL DECK (6" TOTAL THICKNESS).

REINFORCE SLAB-ON-METAL DECK WITH #6 - W4.0 x W4.0 W.W.F. CHAISED 1" CLEAR ABOVE THE TOP OF METAL DECK. AT SPLICES, W.W.F. SHALL BE LAPPED (2) MESH SPACES. W.W.F. SHALL BE SECURED IN CORRECT LOCATION PRIOR TO CONCRETE SLAB PLACEMENT. PROVIDE #4x4'-0" LONG AT 24" c. CENTERED OVER STEEL ORDERS PER TYP. SEE PLAN FOR LOCATIONS WHERE ADDITIONAL REBAR IS REQUIRED. AT OPENINGS THRU THE SLAB-ON-DECK, REINFORCE THE SLAB PER DETAIL.
 - ROOF TOP EQUIPMENT NOTES:
a. RTU-X : ROOF TOP EQUIPMENT DESIGNATION
XXXlbs : TOTAL MAXIMUM WEIGHT OF UNIT, CURB, AND ACCESSORIES; POUNDS
NOTE: SIZE, WEIGHT, AND LOCATION OF ROOF TOP UNITS SHALL BE CONFIRMED BY CONTRACTOR.
b. REFER TO MECHANICAL DRAWINGS FOR ACTUAL LOCATION OF ROOF TOP UNITS.
c. ALL ROOF FRAMING SHALL BE COORDINATED W/ MECHANICAL WORK.
d. AT THE POINT WHERE ROOFTOP UNIT CURBS ARE BEARING ON THE ROOF DECK OVER THE STEEL BEAM THE METAL DECK SHALL BE STRENGTHENED PER DETAIL.
e. AT OPENINGS THRU THE ROOF DECK, REINFORCE THE ROOF DECK PER DETAIL.
 - STEEL BEAM-TO-BEAM FRAMING CONNECTIONS:
a) SEE : FOR BEAM-TO-BEAM SPLICE CONNECTION, TYPICAL. BEAM SPLICES ARE INDICATED: ---
b) SEE : FOR BEAM-TO-BEAM FRAMED CONNECTIONS, TYPICAL UNLESS NOTED OTHERWISE.
c) SEE : FOR BEAM-TO-BEAM CONNECTION WHERE LOCATED AT OR NEAR A STEEL COLUMN, TYPICAL.
 - STEEL BEAM-TO-COLUMN FRAMING CONNECTIONS:
a) SEE : WHERE BEAM IS FRAMING OVER THE TOP OF A TUBE COLUMN, TYPICAL.
b) SEE : WHERE BEAM IS FRAMING INTO THE SIDE OF A TUBE COLUMN, TYPICAL.
 - : INDICATES AN LK&1/2 STEEL ANGLE FOR THE BRICK UNTEL.
--- : STEEL ANGLE SHALL BE HUNG FROM THE STEEL ROOF FRAMING PER DETAILS 4/S3.2.

AGENCY APPROVAL

ALLEY POYNER
MACCHIETTO
ARCHITECTURE

DESIGN DEVELOPMENT

REVISION	DATE
Project Number:	21064
Date:	March 10, 2023

COPYRIGHT © 2022

ROOF FRAMING PLAN



TD2 PROJECT # 748-749

S1.3

NOT FOR CONSTRUCTION