

(RFQ) for selection of a CMAR. Plan sheets will be prepared by the following disciplines: Wastewater (Process), Structural, Civil, Architectural, Geotechnical, Mechanical, Electrical, and Instrumentation & Controls (I&C).

1. The 30% plans will generally show the following:
 - a. Discipline General sheets
 - b. Plant Preliminary Hydraulic Profile
 - c. Process Schematic
 - d. General layout of site improvements such sidewalks, pavement, stormwater ponds
 - e. General piping layouts – pipe and structures will be identified but will not include details such as size, locations, or inverts
 - f. Standard details
 - g. Basic sheet notes to indicate major components
 - h. Selective demolition of major components – includes structures and equipment
 - i. Preliminary foundation design
 - j. General location of major structural accessories such as hatches
 - k. Basic interior building layouts with major equipment, doors, windows, etc.
 - l. Preliminary wall sections and exterior elevations of new structures
 - m. Major wastewater process equipment
 - n. Process piping larger than 4" with flow direction
 - o. Major mechanical equipment for HVAC
 - p. Preliminary layout for ductwork
 - q. Preliminary potable water, plant water, drains, and natural gas piping
 - r. Preliminary lighting plans
 - s. Basic power and instrumentation plan showing major equipment
 - t. Preliminary one-line diagrams for major equipment
 - u. Preliminary process flow diagrams as the basis for future Process and Instrumentation Diagrams (PIDs)
2. NPDES Permit Major Modification application
 - a. For anticipated construction projects all WWTF must apply for permit modifications to include construction activities and the proposed changes to the WWTF.
 - b. The Minnesota Pollution Control Agency (MPCA) has indicated that the permit modification should be done early in the process due to length of time needed for preparing the modified permit, Environmental Protection agency (EPA) review, and for public notice. Please note that the EPA review time may be longer than typical due to the City's request to expand capacity and their review of the Antidegradation Review that was prepared to justify certain permit limits for an expanding facility.
 - c. SEH will assist the City in preparing the application for the permit major modification near the end of the 30% design effort.
 - d. This proposal does not include services related to responding to a contested permit or any design changes for the recommended improvements based on comments received from EPA on the permit or the Antidegradation Review. Those services would be considered Additional.
3. The following items will not be included in the 30% design: