

ARCHITECT:

CJC Architects, Inc.
1401 S Denver, Suite B
Tulsa, Oklahoma, 74119

PROJECT:

TULSA PUBLIC SCHOOLS
Maintenance Facility
1555 N 77th E Ave
Tulsa, Oklahoma 74115

ADDENDUM NUMBER ONE

13 December, 2023

THIS ADDENDUM IS HEREBY MADE A PART OF THE CONTRACT DOCUMENTS TO THE SAME EXTENT AS THOUGH IT WAS ORIGINALLY INCLUDED THEREIN, AND IT SHALL SUPERSEDE ANYTHING CONTAINED IN THE PLANS AND SPECIFICATIONS WITH WHICH IT MIGHT CONFLICT.

CLARIFICATIONS:

January 10th will be the bid opening for this project

Masonry infill does not need to be toothed in

Project address is 1555 N 77th E Ave Tulsa, OK 74115

Cover Page, Wallace Design Group is the Civil Engineer

The roof details show a TPO roof and the specs show Multi-ply cold process built up roof. The specs are correct use Multi-ply cold process built up roof.

Electric room B104 wall will go to deck

The roof material is simple light weight concrete on roof decking shown in structural drawings.

The opening in the existing wall header can be supported by a double steel angle.

C401 bollard detail should read J/C800

DRAWINGS:

Sheet A101	Floor Plan – Corridor B102, new CMU wall connection to existing building see detail ASK-1 Plan Detail
Sheet A211	Building Section – Corridor B102, new CMU wall connection to existing building see detail ASK-2 Wall Detail
Sheet A301	Parapet Detail – Detail 4 & 5, parapet to be metal stud and not see new details clouded A301