

GENERAL STRUCTURAL NOTES - 1

GENERAL

- The following notes are **minimum requirements** unless noted otherwise on the structural drawings prepared by DAVID NAIRNE & ASSOCIATES LTD [DNA].
- Read structural drawings in conjunction with all other consultants' drawings, contract documents and specifications.
- Check and verify all dimensions, quantities and site conditions with architectural drawings before commencing with any work. Notify architect of any discrepancies.
- The latest edition of the standards and codes referenced in these notes and on the Structural Drawings shall apply.
- Do not construct from these drawings unless marked "issued for Construction".
- In the event of discrepancies in the specifications, drawings or contract documents, the more stringent requirement shall apply.
- Notes and details specified on the plans and details take precedence over those in General Structural Notes, except for minimum requirements.
- For conditions not explicitly shown, Contractor shall immediately request clarifications from the Structural Engineer.
- Contractor to submit to DNA in writing all proposed alternate products, materials and structural systems for review at least 4 weeks prior to the start of construction.

FIELD REVIEW

- Contractor is responsible for pre-inspecting the work and confirming completeness and conformity with the Structural Contract Documents prior to field review by DNA.
- Notify DNA at least ONE WEEK in advance for field review of the following:
 - Concrete reinforcement: Prior to each concrete pour
 - Structural steel: Prior to concealment
 - Wood framing: Prior to concealment
- Work found to be incomplete or deficient may require additional field reviews at additional cost to the Contractor.
- Our field review consists of a periodic review of the structural work only. It is not carried out for the Contractor's benefit, and it does not make DNA guarantors of the Contractor's work. The Contractor is responsible for his own quality control and shall perform the work with good workmanship in the conformance with the Contract Documents.

SUBMITTALS AND SHOP DRAWINGS

- Contractor is responsible for overall coordination of sub-tenders.
- Suppliers shall prepare for DNA and submit to the General Contractor a Digital and complete set of Shop Drawings for general compliance review prior to fabrication. Each sheet shall be sealed and signed by a Professional Engineer registered in the Province of Yukon, who will be the **Specialty Structural Engineer** responsible for the integrity of his/her design. **DNA will NOT review or assume responsibility for such matters as dimensions or quantities or the Contractor's safety measures or methods of construction.**
- Incomplete sets of Shop Drawings, or Shop Drawings prepared using reproductions of DNA Structural Drawings will **NOT** be accepted.
- Shop drawings and other submittals of pre-engineered or proprietary structural elements shall clearly indicate type, position, and connection to elements of the Primary Structural System as well as the criteria and loads used for the design.
- Submittals must be reviewed by the General Contractor prior to DNA's review.
- Where required by the following sections of these General Structural Notes, proprietary products, connections and other structural elements which have been designed by Specialty Structural Engineers shall be inspected by those engineers at the appropriate stage of construction, at which time observations and deficiencies in the work shall be reported in writing to the SER (DNA).
- Where required by the following sections of these General Structural Notes, each Specialty Structural Engineer shall submit to DNA Letters of Assurance Schedules B and C-B, or S-B and S-C, sealed and signed, clearly outlining areas of responsibility. Refer to the following sections for specific Shop Drawing requirements.
- After review, the drawings will be stamped and initialed to show one of the following:
 - NOT REVIEWED - Shows work not within Structural consultant's scope of work.
 - REVISE AND RESUBMIT - Correct and resubmit for review prior to fabrication.
 - REVIEWED AS MODIFIED - Released for fabrication after revisions noted are made.
 - REVIEWED - Released for fabrication.

CONSTRUCTION

- Drawings show completed structures only. Contractor is responsible for temporary bracing for all building elements against construction loading conditions and for construction erection procedures. Temporary support to be designed by a Professional Engineer registered in the Province of British Columbia in accordance with WorkSafeBC regulations and as required by local building authorities.
- It is the sole responsibility of the Contractor to ensure that no part of the work is subjected to a load which will endanger the safety of the building or workers.
- Protect structural work from adverse weather conditions and moisture prior to, during and after installation.
- Contractor to compare all design drawings, dimensions and site conditions and notify DNA of any discrepancies prior to proceeding with the work.
- Contractor to submit to DNA in writing all proposed alternate products and structural systems, including technical specifications where required, for review and approval.
- Contractor shall review the concrete pour plan with DNA prior to construction.

STRUCTURAL DESIGN

- The new construction for this base building has been designed by DNA in accordance with:
Part 4 of the 2020 National Building Code of Canada (NBC):
- Climatic Design Criteria:
 - Ground Snow Load (1 in 50 year) S_s (1/50) = 3.0 kPa
 - Rain Load (1 in 50 year) S_r (1/50) = 0.1 kPa
 - Importance Factor for Snow Load I_s = 1.15
 - 24-Hour Rain 38 mm
 - Hourly Wind Pressure (1/10 year) q (1/10) = 0.26 kPa
 - Hourly Wind Pressure (1/50 year) q (1/50) = 0.34 kPa
 - Importance Factor for Wind Load I_w = 1.15
 - Wind Internal Pressure Category = 2.0
- Minimum Design Live Loads:

Area	Occupancy/Notes	Specified Load	
Main floor S.O.G.	Typical	4.8 kPa	(100 psf)
Second Storey Floor	Typical	2.4 kPa	(50 psf)
Storage Areas		4.8 kPa	(100 psf)
Corridors	> 1200 (4 ft) wide	4.8 kPa	(100 psf)
Exits and stairs		4.8 kPa	(100 psf)
Roof/top Patio Areas		4.8 kPa	(100 psf)
Basic roof snow load	+ build up where applicable	2.9 kPa	(61 psf)
Handrails and Guards		Per Part 4 of the Building Code	

- Seismic Data:
 - Ground Motions $S_a(0.2)$ = 0.475 $S_a(0.5)$ = 0.499 $S_a(1.0)$ = 0.386 $S_a(2.0)$ = 0.231 $S_a(5.0)$ = 0.103 P_GA = 0.195
 - Peak Ground Acceleration
 - Site Class D (Assumed)
 - Importance Factor I_e = 1.3
 - Ductility NS direction: R_d = 3.0 R_o = 1.7 EW direction: R_d = 3.0 R_o = 1.7
 - Lateral Seismic force (factored) V = 0.13 x W
 - Plywood diaphragms are assumed to be ductile.
- See drawings for specific loads and loading conditions. Specialty Engineers to be responsible for identifying specific loading conditions within their scopes of work.

SITE PREPARATION AND FOUNDATIONS

- Building foundations have been designed in accordance with a Geotechnical Report Prepared by: Tetra Tech File No: 704-ENG-WARC03759-02 Dated: November 26, 2021
- Site Preparation:
 - Contractor to prepare site in accordance with Geotechnical Report and notify Geotechnical Engineer for field review of site preparations prior to foundation construction.
 - Protect native soils from softening and frost. Remove all softened or frost damaged soils prior to placement of reinforcement and concrete. Protect bearing soils from freezing after footing construction.
 - Excavations to be free of water prior to and during concrete placement. Provide adequate means of removing water from excavations and trenches.
 - If building site is underlain by methane generating soils, refer to other consultant's report and drawings for design of methane control measures.
 - If building site is underlain by compressible soils, the building foundation design is based on the site being preloaded with mineral fill to induce primary consolidation settlement of the underlying compressible soils prior to foundation construction.
- Foundation design:
 - Bearing soil: Sand and gravel
 - Serviceability Limit State bearing capacity 400kPa (8400 psf) - Strip 600kPa (12500 psf) - Spread 220kPa (4600 psf) - Strip 220kPa (4600 psf) - Spread
 - Factored Ultimate Limit State bearing capacity
- Minimum footing width:
 - Pad footing 900mm (3'-0")
 - Strip footing 450mm (1'-6")
- Variable soil conditions that result in lower allowable soil bearing conditions may require revision to foundation design.
- Minimum frost cover to be _____ at interior heated space and _____ at exterior isolated footings per Geotechnical Report
- Building design based on the following long-term settlements estimated by the Geotechnical Engineer:
 - Total settlements: = 25mm (1.0 inch)
 - Differential settlements: = _____mm (____ inch)
 - Angular distortion: = _____
- Provide formwork for full specified depth of footings and provide level footing base to allow uniform clear cover to reinforcement and to prevent sloughing of adjacent soil into footing form.
- Loose or wet sub-base under footings may require removal, sub excavation and replacement with structural fill. Refer to Geotechnical Report for details.
- Compact fills in maximum lifts and to densities as noted in the Geotechnical Report or as directed by the Geotechnical Engineer, and test for compaction at sufficient intervals to verify conformance.
- Provide a minimum of 150mm (6") of well graded sand and gravel below all interior and exterior slabs-on-grade on prepared sub-base. Compacted to approval of Geotechnical Engineer.
- Securely tie down all anchor bolts and embedded items to formwork prior to concrete pour.
- Centre footings under columns/walls unless noted otherwise.
- Retaining wall and basement wall backfill requirements:
 - Backfill material behind retaining walls to be compacted, clean free-draining granular backfill.
 - Install drainage system behind wall designed by others.
 - Do not backfill behind retaining walls until concrete has achieved a minimum strength of 25 MPa.
 - Do not backfill behind basement walls, or other walls to be connected to the floor or roof structure, until after completion of the floor and roof system to approval of DNA.

CONCRETE

- Specifications:
 - Standards: CAN/CSA A23.1, CAN/CSA A23.2, CAN/CSA A23.3
 - Cement: Portland Cement Type G.U. in accordance with CSA A3001
 - Coarse Aggregate: 19mm (3/4") maximum U.N.O.
 - Mix Design to Alternative 1 per Table below:

Locations	28 - Day Compressive Strength, MPa	W/C Ratio	Air Entrain %	Slump (mm)	Exposure Class	Cement Type	See Notes
Interior Footings	25	0.60	1 to 4	80 ± 30	N	G.U.	N/A
Exterior Footings	25	0.55	4 to 7	80 ± 30	F-2	G.U.	N/A
Foundation walls (Exposed)	25	0.55	4 to 7	80 ± 30	F-2	G.U.	N/A
Interior slab-on-grade	30	0.55	1 to 4	80 ± 30	N	G.U.	2(C), 3
Exterior slab-on-grade	32	0.45	5 to 8	80 ± 30	C-2	G.U.	2(A), 3
Ramp slab-on-grade - vehicular traffic	35	0.40	5 to 8	80 ± 30	C-2	G.U.	2(B), 3
Exterior slab-on-grade - vehicular traffic	32	0.45	5 to 8	80 ± 30	C-2	G.U.	2(A), 3
Interior floor topping	25	0.45	-----	80 ± 30	N	G.U.	2(A), 7
Interior walls & columns/pedestals	25	0.60	-----	80 ± 30	N	G.U.	N/A
Exterior walls & columns/pedestals	25	0.55	4 to 7	80 ± 30	F-2	G.U.	N/A
Tank base slab	32	0.45	4 to 7	80 ± 30	F-2	G.U.	2(A), 6

Notes: Where referenced in notes column of the table above.

- Slab-on-grade in exposed interior areas to be wet cured.
- Slab and Floor Finish Classifications as per CSA A23.1:

Class	Description	Straight edge Tolerance	F _F	F _L	SWi
A	Conventional (smooth)	± 8mm	20	15	5mm
B	Conventional (non slip)	± 12mm	15	15	8mm
C	Moderately Flat	* ± 3mm *	30	20	3mm
- See CSA A23.1 for finishing procedure.
- Sawcut crack control joint as soon as possible within 12 hours of slab finishing. See Architectural and Structural drawings for locations and details.
- Hand tool crack control joint. See Architectural drawings for locations.
- Add polypropylene fibres to concrete mix at plant to reduce non-structural cracking. Fibres to be Fibermesh 'MD' as manufactured by Fibermesh Division, Synthetic Industries, at an application rate of 0.9 kg/m³ to 1.8 kg/m³. Actual application rate and concrete mix design to be reviewed by Fibermesh and concrete supplier.
- KRYTON KIM ADMIXTURE: Concrete strength noted is minimum required for structural design; higher strengths may be required based on KIM mix requirements. Minimum Portland cement content shall be 250 kg/m³. Maximum W/C ratio shall be 0.45. KIM waterproofing admixture to be added into the concrete mix at the time of batching at 2% by weight of the cementitious materials. Contact Kryton International Incorporated at 604-324-8280 for application instructions and specifications.
- Max aggregate size of 3/8" (10mm) for masonry grout and concrete topping.

- Admixtures: Admixtures to approval of DNA. Calcium Chloride not allowed. Admixtures to conform to requirements of ASTM C260 (air entrainment) and ASTM C494 (chemical).
- Testing: Test concrete as per CSA A23.1 and A23.2: Min one test of three cylinders per Class per day. Additional tests required per A23.1 and A23.3. Additional field-cured cylinders required in hot and cold weather conditions.
 - Grout: Non-shrink cementitious grout, minimum 30MPa at 3 days and minimum 55MPa at 28 days.
- Concrete to be well consolidated with mechanical vibrator.
- Protect concrete from all harmful substances and adverse weather conditions during construction.
- No embedded items, including blockouts, nailers, conduits, ducts, pipes, sleeves, etc., are permitted in concrete formwork unless specifically authorized by DNA.
- All concrete work, including footings, walls, slabs, curbs, and topping, shall be reinforced except skincoats unless otherwise noted.
- Unless otherwise noted, provide minimum bottom reinforcing in slabs as below:

Slab thickness	Temperature reinforcing each way
150 (6")	10M @ 300 (12")
175 (7")	10M @ 250 (10")
200 (8")	15M @ 450 (18")
225 (9")	15M @ 400 (16")
250 (10")	15M @ 400 (16")
- Submittals: Contractor shall pay for and provide the following submittals:
 - Mix designs
 - Concrete test results

REINFORCING STEEL

- All work shall meet the requirements of the Canadian Standards Association [CSA] and the American Society for Testing and Materials [ASTM].
- Deformed bars shall conform to CSA G30.18 Grade 400 MPa (F_y=60,000 psi) with:
 - Lapped tension splices in accordance with CAN3-A23.3 as follows:

BAR SIZE	10M	15M	20M	25M	30M	WWM	
BASIC TENSION LAP SPLICE	mm (in)	450 (18)	630 (24)	780 (30)	1290 (50)	1700 (67)	300 (12)
FULL TENSION LAP SPLICE	mm (in)	620 (24)	880 (36)	1090 (43)	1810 (72)	2400 (94)	-
 - Detail reinforcement to stagger splices and minimize usage of splices U.N.O. on plans. Splicing of reinforcing steel shall meet the requirements of CAN3-A23.3.
 - Horizontal reinforcement shall be continuous around corners with bends or corner bars.
 - All concrete shall be reinforced. Concrete not explicitly detailed shall have the following minimum reinforcement:
 - Columns: 1% of gross area of section. 15M ties spaced at least 1/2 least dimension of column.
 - Beams: 0.35% of gross area of section. 15M ties spaced at 1/2 depth of beam.
 - Slabs and Walls: 0.2% of gross area of section each way and perimeter beam as detailed.
- Maintain concrete cover to reinforcing as follows when not explicitly detailed:

STRUCTURAL MEMBER	EXPOSURE TO WEATHER	
	EXPOSED	NOT EXPOSED
For beams, girders, columns and piles: Principal reinforcement, 35M and smaller	mm (in)	50 (2) 40 (1 1/2)
For ties, stirrups and spirals:	mm (in)	40 (1 1/2) 30 (1 1/8)
For slabs, walls and joists, 20M and smaller:	mm (in)	40 (1 1/2) 20 (3/4)
For bars with diameter d larger than listed above, cover shall be min. 50mm (and need not be > 50mm)		1.5 d 1.0 d
The ratio of the cover to the nominal maximum aggregate size shall be minimum:		1.5 d 1.0 d
Formed surface exposed to ground or weather:	mm (in)	50 (2)
When cast against, and permanently exposed to, earth:	mm (in)	75 (3)

The cover for a bundle of bars shall be the same as that for a single bar with an equivalent area.

- Maintain concrete cover to reinforcing of tilt-up panels as follows:

CLEAR COVER TO MAIN REINFORCING		CLEAR COVER TO TIES & STIRRUPS	
OUTSIDE FACE OF PANEL	mm (in)	25 (1)	20 (3/4)
INSIDE FACE OF PANEL	mm (in)	20 (3/4)	40 (1 1/2)
EDGE OF PANEL	mm (in)	50 (2)	
- Placement:
 - Openings in walls and slabs:
 - Do not cut typical reinforcement at openings, but shift to each side of opening.
 - Provide 1 - 15M x 4'-0"LG diagonal bar 25mm (1") clear from corner of opening.
 - Openings ≤ 600 (24") square: Provide 2-15M each side, extending 600 (24").
 - Openings > 600 (24") square: Provide extra reinforcing as directed on Site by DNA.
 - Provide dowels to match size and spacing of vertical and horizontal reinforcement.
- All reinforcement required to be welded to connection plates shall be Grade 400W (Weldable). Weld steel in conformance with CSA W186.
- All reinforcement to be bent in the field shall be Grade 400W (Weldable).
- Ensure all bars are securely tied and chained to maintain specified cover and prevent displacement during concrete placement. For surfaces exposed to weather, provide non-corrosive chairs.
- Wet doweling of reinforcement is not acceptable unless approved in advance by DNA.
- All reinforcing steel shall be clean of substances that will affect its bond to concrete.
- Bars damaged in the field may require replacement as directed by DNA.
- For tension splices, no more than 50% of the bars shall be splices at any one location.
- Where drill and epoxy reinforcing is required the following minimum embedment must be applied, unless directed otherwise in writing by DNA. Drill and epoxy with Hilti RE 500 V3 to develop reinforcing.

Reinforcing Bars	Minimum Embedment	Reinforcing Bars	Minimum Embedment
10M	240mm	20M	540mm
15M	400mm	25M	850mm

- Provide minimum of 3000 lbs of extra reinforcement (10M + 15M) to be used as directed by DNA.

ABBREVIATIONS

ABBREV.	DENOTES	ABBREV.	DENOTES	ABBREV.	DENOTES
Ø	DIAMETER	EA	'EACH'	o/c	'ON CENTER'
±	PLUS OR MINUS	E/F	'EACH FACE'	O/F	'OUTSIDE FACE'
ALT	'ALTERNATE'	EL	'ELEVATION'	OVSJ	'OPEN WEB STEEL JOIST'
ARCH	'ARCHITECT(URAL)'	EQ	'EQUAL(LY)'	PL or □	'PLATE'
BCE	'BOTTOM CHORD EXTENSION'	E/S	'EACH SIDE'	PLY	'PLYWOOD'
		E/W	'EACH WAY'	PSL	'PARALLEL STRAND LUMBER'
BLDG	'BUILDING'	EXIST	'EXISTING'		
BL	'BOTTOM LOWER LAYER'	FDN	'FOUNDATION'	P.T.	'PRESSURE TREATED'
BOT	'BOTTOM'	F/H	'FULL HEIGHT'	REINF	'REINFORCE(MENT)' or 'REINFORCING'
BTWN	'BETWEEN'	FTG	'FOOTING(S)'	REQ'D	'REQUIRED'
B/U	'BUILT UP'	GA	'GAUGE'	r/w	'REINFORCED WITH'
BUL	'BOTTOM UPPER LAYER'	GALV	'GALVANIZE(D)'	SIM	'SIMILAR'
B/W	'BOTH WAYS'	H1E	REINFORCING BAR WITH 90° BEND ONE END	S.O.G.	'SLAB-ON-GRADE'
CANT	'CANTILEVER(ED)'	H2E	REINFORCING BAR WITH 90° BEND BOTH ENDS	STAG	'STAGGERED'
C.J.	'SLAB CONTROL/CONSTRUCTION JOINT'	HD	'HOLDOWN(S)'	SW	'SHORT WAY'
		H2	'HOLDOWN(S)'	SYM	'SYMMETRY' or 'SYMMETRICAL'
CL	'CLEAR(ANCE)'	HORIZ	'HORIZONTAL'	T&B	'TOP AND BOTTOM'
□	'CENTRELINE'	I/F	'INSIDE FACE'	T&G	'TONGUE AND GROOVE'
COL	'COLUMN'	LG	'LONG'	THK	'THICK'
CONC	'CONCRETE'	LL	'LIVE LOAD'	TLL	'TOP LOWER LAYER'
CONT	'CONTINUOUS'	LLH	STEEL ANGLE 'LONG LEG HORIZONTAL'	T.O.	'TOP OF'
C/S	'COUNTERSINK'	LLV	STEEL ANGLE 'LONG LEG VERTICAL'	TRANS	'TRANSVERSE'
c/w	'COMPLETE WITH'			THRU	'THROUGH'
DBL	'DOUBLE'	LONGIT	'LONGITUDINAL'	TUL	'TOP UPPER LAYER'
DIM	'DIMENSION'	LSL	'LAMINATED STRAND LUMBER'	TYP	'TYPICAL'
DP	'DEEP'			U.N.O.	'UNLESS NOTED OTHERWISE'
DS	'DRAG STRUT'	LVL	'LAMINATED VENEER LUMBER'	u/s	'UNDERSIDE OF'
DWG	'DRAWING(S)'	LW	'LONG WAY'	VERT	'VERTICAL'
		MECH	'MECHANICAL'	w/	'WITH'
		N.T.S.	'NOT TO SCALE'		


COMMUNITY CENTRE DRAWING INDEX

STRUCTURAL DRAWING INDEX	
S1.1	GENERAL STRUCTURAL NOTES - 1
S1.2	GENERAL STRUCTURAL NOTES - 2
S2.1	BASEMENT FOUNDATION PLAN
S2.2	MAIN FLOOR FRAMING / FOUNDATION PLAN
S2.3	UPPER FLOOR FRAMING PLAN
S2.4	ROOF FRAMING PLAN
S2.5	ROOF FRAMING PLAN - UPPER STRUCTURES
S2.1A	BASEMENT FOUNDATION PLAN - A
S2.2A	MAIN FLOOR FRAMING / FOUNDATION PLAN - A
S2.3A	UPPER FLOOR FRAMING PLAN - A
S2.4A	ROOF FRAMING PLAN - A
S2.5A	ROOF FRAMING PLAN - UPPER STRUCTURES - A
S2.2B	MAIN FLOOR FOUNDATION PLAN - B
S2.3B	UPPER FLOOR FRAMING PLAN - B
S2.4B	ROOF FRAMING PLAN - B
S2.5B	ROOF FRAMING PLAN - UPPER STRUCTURES - B
S3.0	TYPICAL FOUNDATION DETAILS - 1
S3.1	TYPICAL FOUNDATION DETAILS - 2
S3.2	FOUNDATION DETAILS - 1
S3.3	FOUNDATION DETAILS - 2
S3.4	FOUNDATION DETAILS - 3
S3.5	FOUNDATION DETAILS - 4
S4.0	TYPICAL FRAMING DETAILS - 1
S4.1	TYPICAL FRAMING DETAILS - 2
S4.2	FLOOR FRAMING DETAILS - 1
S4.3	FLOOR FRAMING DETAILS - 2
S4.4	FLOOR FRAMING DETAILS - 3
S4.5	FLOOR FRAMING DETAILS - 4
S4.6	FLOOR FRAMING DETAILS - 5
S5.0	TYPICAL ROOF FRAMING DETAILS
S5.1	ROOF FRAMING DETAILS - 1
S5.2	ROOF FRAMING DETAILS - 2
S5.3	ROOF FRAMING DETAILS - 3
S4.4	ROOF FRAMING DETAILS - 4
S5.5	ROOF FRAMING DETAILS - 5
S5.6	ROOF FRAMING DETAILS - 6
S6.1	WINDOW FRAMING ELEVATION DETAILS
S6.2	STAIR FRAMING AND DETAILS

ENERGY CENTRE DRAWING INDEX

STRUCTURAL DRAWING INDEX	
EC-S1.1	GENERAL STRUCTURAL NOTES
EC-S2.1	FOUNDATION & FRAMING PLANS
EC-S2.2	ROOF FRAMING PLAN
EC-S3.1	FOUNDATION DETAILS - 1
EC-S3.2	FOUNDATION DETAILS - 2
EC-S3.3	DIAPHRAGM AND ROOF DETAILS
EC-S3.4	ROOF FRAMING DETAILS
EC-S3.5	MISCELLANEOUS DETAILS

KEY PLAN



COPYRIGHT AND USE OF DOCUMENTS:

COPYRIGHT FOR THE ARCHITECTS INSTRUMENTS OF SERVICE BELONGS TO THE ARCHITECTS. SUBSIDIARY OR DISTRIBUTION OF THE ARCHITECTS INSTRUMENTS OF SERVICE, INCLUDING ALL SOFTWARE AND ELECTRONIC MEDIA TO MEET OPTICAL REGULATORY REQUIREMENTS OR FOR OTHER PURPOSES IN CONNECTION WITH THE PROJECT IS NOT TO BE CONTINUED REPRODUCTION OR REPRODUCTION OF THE ARCHITECTS INSTRUMENTS OF SERVICE FOR INFORMATION AND REFERENCE IN CONNECTION WITH THE CLIENTS USE AND OCCUPANCY OF THE PROJECT. COPIES MAY ONLY BE USED FOR THE PURPOSES OF THE ARCHITECTS INSTRUMENTS OF SERVICE FOR INFORMATION AND REFERENCE IN CONNECTION WITH THE CLIENTS USE AND OCCUPANCY OF THE PROJECT. INTENDED AND FOR A ONE-TIME USE, ON THE SAME SITE, AND FOR THE SAME PROJECT. IF THIS CLIENT ONLY AND MAY NOT BE OFFERED FOR SALE OR TRANSFER WITHOUT THE EXPRESS WRITTEN CONSENT OF THE ARCHITECT. EXCEPT FOR REPRODUCTION OF THE ARCHITECTS INSTRUMENTS OF SERVICE, INCLUDING ALL SOFTWARE AND ELECTRONIC MEDIA, AND INFORMATION, SHALL NOT BE USED FOR RENOVATIONS, ADDITIONS, OR ALTERATIONS TO THE PROJECT OR ON ANY OTHER PROJECT WITHOUT A WRITTEN LICENSE FROM THE ARCHITECT. FOR THE LIMITED OR REPEAT USE OF THE DOCUMENTS.

INSTRUMENTS OF SERVICE ARE THE DESIGN AND DRAWINGS, SPECIFICATIONS AND REPORTS PREPARED BY OR ON BEHALF OF THE ARCHITECT INCLUDING BUT NOT LIMITED TO PLANS, SKETCHES, DRAWINGS, GRAPHIC REPRESENTATIONS AND SPECIFICATIONS, COMPUTER GENERATED DESIGNS AND MATERIAL.

ISSUED FOR ADDENDUM--03
2025.01.31

7

ISSUED FOR ADDENDUM--02
2025.01.24

6

ISSUED FOR BUILDING PERMIT
2025.01.23

5

ISSUED FOR TENDER
2024.12.17

4

ISSUED FOR REVIEW 100%
2024.11.12

3

ISSUED FOR REVIEW 65%
2024.10.11

2

ISSUED FOR REVIEW 35%
2024.08.30

1

REVISIONS

DESIGN BY
LG/MG

CHECKED BY
JLUM

DRAWN BY
SAL/DA

DRAWING DATE
03/15/21

SCALE
-

CONSULTANT