

THE SAYLES RESIDENCE - L30 (2386) NG, DUPLEX

PROJECT DESCRIPTION

AREAS:
TOTAL LIVING - 2,418 SF
MAIN FLOOR - 612 SF / UNIT
UPPER FLOOR - 597 SF / UNIT
COVERED EXTERIORS - 72 SF / UNIT
STORIES: 2
CONSTRUCTION: WOOD, LIGHT FRAME
SITE ADDRESS: 39600 EVANS STREET
SANDY, OR 97055
CITY OF SANDY



DRAWINGS INDEX

CS	COVER SHEET
N	NOTES
EO	ENERGY PATH - OREGON

A1	EXTERIOR ELEVATIONS
A2	MAIN FLOOR PLAN
A2.1	UPPER FLOOR PLAN
A3	FOUNDATION PLAN
A3.1	MAIN FLOOR JOIST PLAN
A4	MAIN FLOOR FRAMING PLAN
A4.1	UPPER FLOOR JOIST PLAN
A4.2	UPPER FLOOR FRAMING
A5	ROOF PLAN
A6	BUILDING SECTION A
A7	CABINET DETAILS

AD1	DETAILS
AD2	DETAILS
AD3	DETAILS
AD4	DETAILS
AD5	DETAILS
AD6	DETAILS
AD7	DETAILS
AD8	DETAILS
AD9	DETAILS
AD10	DETAILS
AD11	DETAILS
AD12	DETAILS
AD13	DETAILS

FJ1	IWP MAIN FLOOR JOIST LAYOUT
FJ2	IWP UPPER FLOOR JOIST LAYOUT

S1.0	WCE UPPER SHEARWALL PLAN
S1.1	WCE MAIN SHEARWALL PLAN
S1.2	WCE FOUNDATION SHEARWALL PLAN
S5.0	WCE STRUCTURAL DETAILS
S5.1	WCE STRUCTURAL DETAILS

CODE INFORMATION

2021 ORSC
2021 ORSC - CHAPTER 11 ENERGY CODE

GENERAL NOTES

1) CONTRACTOR TO FIELD VERIFY ALL EXISTING CONDITIONS AND THE CONSTRUCTION DRAWINGS PRIOR TO COMMENCING WORK. CONTRACTOR TO NOTIFY ADAIR HOMES IMMEDIATELY OF ANY DISCREPANCIES, ERRORS OR OMISSIONS.

2) DO NOT SCALE DRAWINGS. USE DIMENSIONS SHOWN. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CROSS CHECK DETAILS AND DIMENSIONS SHOWN ON THE ARCHITECTURAL DRAWINGS WITH RELATED REQUIREMENTS ON THE STRUCTURAL AND OTHER DRAWINGS AS APPLICABLE. NOTIFY ADAIR HOMES OF ANY DISCREPANCIES BEFORE COMMENCING WORK

3) WHERE NO SPECIFIC STANDARDS ARE APPLIED TO A MATERIAL OR METHOD OF CONSTRUCTION TO BE USED IN THE WORK, ALL SUCH MATERIALS AND METHODS ARE TO MAINTAIN THE STANDARDS OF THE INDUSTRY.

4) ALL CONSTRUCTION WORK SHALL BE DONE IN COMPLIANCE WITH THE LATEST EDITION OF THE APPLICABLE BUILDING CODE AS AMENDED BY THE STATE AND ALL OTHER STATE AND LOCAL REQUIREMENTS THAT APPLY.

5) MATERIALS, EQUIPMENT, ETC., NOT INDICATED ON
DRAWINGS OR SPECIFIED HEREIN BUT REQUIRED FOR THE
SUCCESSFUL COMPLETION OF THE INSTALLATION SHALL BE
HELD TO BE IMPLIED AND SHALL BE FURNISHED BY THE
CONTRACTOR FOR NO ADDITIONAL COST.

6) ERRORS OR OMISSIONS IN ANY SCHEDULE OR DRAWING DO NOT RELIEVE THE CONTRACTOR FROM RESPONSIBILITY FOR THE WORK INTENDED IN THE DRAWINGS OR SPECIFICATIONS.

DESIGN CRITERIA

SEISMIC DESIGN CATEGORY: D0
WIND SPEEDS: < OR = TO 130mph Vult
EXPOSURE CATEGORY: B
SOILS BEARING CAPACITY: 1500#
ROOF SNOW LOAD: 30#
FROST DEPTH: 18"

TYPICAL ABBREVIATIONS

CL	CENTER LINE	CPT	CARPET	HVAC	HEATING, VENTILATION & AIR	SYM	SYMBOL OR SYMMETRICAL
°	DEGREE(S)	CTR	CENTER		CONDITIONING	T&B	TOP AND BOTTOM
"	INCH(ES)	CTSK	COUNTERSINK	LTBD	LOCATION TO BE DETERMINED	T&G	TONGUE AND GROOVE
'	FOOT (FEET)	DED	DEDICATED	MAX	MAXIMUM	TEMP	TEMPERED OR TEMPORARY
#	NUMBER OR POUND	DIA	DIAMETER	MIN	MINIMUM	TKC	TIGHT KNOT CEDAR
x	BY (2 x 4)	DIM	DIMENSION	MTL	METAL	TO	TOP OF
AB	ANCHOR BOLT	DN	DOWN	NTS	NOT TO SCALE	TOD	TOP OF DECK
A/C	AIR CONDITIONING	DW	DISHWASHER	OBS	OBSCURE	TOS	TOP OF SLAB
ADJ	ADJUST(ABLE)	EA	EACH	OC	ON CENTER	TOW	TOP OF WALL
AFF	ABOVE FINISHED FLOOR	EXT	EXTERIOR OR EXTENSION	OPP	OPPOSITE	TYP	TYPICAL
ALT	ALTERNATE, ALTERNATIVE	FF	FINISHED FLOOR	OPT.	OPTIONAL	UM.	UNDERMOUNT
BD	BOARD	FDN	FOUNDATION	OSB	ORIENTED STRAND BOARD	UNO	UNLESS NOTED OTHERWISE
BLDG	BUILDING	FLR.	FLOOR	PL	PLATE	VERT	VERTICAL
BLK	BLOCK	FO	FACE OF	PT	PRESSURE TREATED	VIF	VERIFY IN FIELD
BLKG	BLOCKING	FOC	FACE OF CONCRETE	PWD	PLYWOOD	W/	WITH
BS	BOTH SIDES	FOF	FACE OF FINISH	QTY	QUANTITY	WD	WOOD
CL	CENTER LINE	FOS	FACE OF STUD	REQ'D	REQUIRED	WH	WATER HEATER
CLG	CEILING	GYP	GYPSUM	RM	ROOM	W/O	WITHOUT
CLO	CLOSET	GYP BD	GYPSUM BOARD (SHEETROCK)	RO	ROUGH OPENING		
CLR	CLEAR(ANCE)	HDW	HARDWARE	RS	ROUGH SAWN		
CMFT.	COMFORT HEIGHT	HT	HEIGHT	STN	STONE VENEER		
CONC.	CONCRETE			SIM	SIMILAR		

REVISION HISTORY

[illegible]

2021 ORSC

2386 - DUPLEX

© COPYRIGHT 2023
IR HOMES INC.



ADAIR HOMES, INC
1311 SE CARDINAL COURT
SUITE 100
VANCOUVER, WA 98683

HMS MODEL CODE:

PLAN ORIENTATION: STANDARD

Garage Configuration:

COVER SHEET

SCALE: _____
DATE: 06/15/2023
DRAFTED BY: ES
REV: _____

PAGE:

SC