

GENERAL NOTES

A. GENERAL INFORMATION

1. READ STRUCTURAL DOCUMENTS IN CONJUNCTION WITH CONTRACT DOCUMENTS, WHICH INCLUDE, BUT ARE NOT LIMITED TO, ARCHITECTURAL, MECHANICAL, AND ELECTRICAL DOCUMENTS.
2. CONTRACTOR TO BE RESPONSIBLE FOR CHECKING SITE CONDITIONS AGAINST DOCUMENTS, BEFORE PROCEEDING WITH THE WORK, AND REPORT DISCREPANCIES TO THE CONSULTANT.
3. CONTRACTOR TO PROVIDE LABOUR, MATERIALS, AND EQUIPMENT TO COMPLETE ALL STRUCTURAL WORK INDICATED.
4. CARRY OUT CONSTRUCTION OPERATIONS, INCLUDING THE INSTALLATION OF TEMPORARY GUYING AND SHORING REQUIRED, ENSURING THAT THE EXISTING STRUCTURE OR MEMBERS ALREADY ERECTED ARE NOT LOADED IN EXCESS OF THEIR SAFE LOAD CARRYING CAPACITY.
5. STRUCTURAL DOCUMENTS DO NOT NECESSARILY SHOW ALL OPENINGS AND SLAB VARIATIONS REQUIRED. THE CONTRACTOR SHALL REFER TO ARCHITECTURAL, MECHANICAL, AND ELECTRICAL DRAWINGS FOR THE EXACT LOCATION, NUMBER, AND SIZE OF OPENINGS, TRENCHES, PITS, SUMPS, SLEEVES, AND DEPRESSIONS. PROVIDE STRUCTURAL FRAMING AT THESE LOCATIONS IN ACCORDANCE WITH THE APPLICABLE TYPICAL DETAIL.

B. REFERENCE STANDARDS/CODES AND ACTS

1. CONFORM WITH THE 2012 BUILDING CODE (ONTARIO REGULATION 332/12, AMENDED BY ONTARIO REGULATIONS 191/14, 563/17 AND 88/19), AND ANY APPLICABLE ACTS OF ANY AUTHORITY HAVING JURISDICTION, AND THE FOLLOWING:

REF	CODE	TITLE
a)	CAN/CSA-S16	LIMIT STATES DESIGN OF STEEL STRUCTURES.
b)	CAN/CSA G40.20/G40.21	STRUCTURAL QUALITY STEEL.
c)	O86	ENGINEERING DESIGN IN WOOD (LIMIT STATES DESIGN).
d)	CSA-A371	MASONRY CONSTRUCTION FOR BUILDINGS.
e)	S304.1	DESIGN OF MASONRY STRUCTURES

2. ALL STANDARDS AND PUBLICATIONS REFERENCED BY THE STANDARDS NOTED ABOVE ARE TO APPLY.
3. WHERE THERE ARE DIFFERENCES BETWEEN THE DOCUMENTS AND THE STANDARDS, CODES AND ACTS, THE MOST STRINGENT SHALL GOVERN.

C. SUBMITTALS

1. SUBMIT FOR REVIEW BY THE VARIOUS CONSULTANTS, DETAILED INFORMATION FOR ALL TEMPORARY AND PERMANENT STRUCTURAL WORK. THIS INCLUDES, BUT IS NOT LIMITED TO:

ITEM	SUBMISSION REQUIRED	SUBMISSION TO BE SEALED BY PROFESSIONAL ENGINEER	COMMENTS
TEMPORARY SHORING	YES	YES	
STRUCTURAL STEEL SHOP DRAWINGS	YES	YES	

1. CONTRACTOR SHALL ALLOW FOR A TURN AROUND TIME OF 5 WORKING DAYS FOR THE REVIEW OF THESE SUBMISSIONS.
2. OUR REVIEW OF THE SHOP DRAWINGS IS ONLY FOR GENERAL CONFORMITY WITH STRUCTURAL CONTRACT DOCUMENTS AND SPECIFICATIONS. COMMENTS MADE ON THE SHOP DRAWINGS DURING THIS REVIEW DO NOT RELIEVE THE CONTRACTOR FROM COMPLIANCE WITH THE REQUIREMENTS OF THE STRUCTURAL CONTRACT DOCUMENTS AND SPECIFICATIONS, NOR DO THEY AUTHORIZE ANY CHANGES TO THE CONTRACT. REVIEW OF A SPECIFIC ITEM SHALL NOT INCLUDE REVIEW OF AN ASSEMBLY OF WHICH THE ITEM IS A COMPONENT. THE CONTRACTOR'S RESPONSIBILITIES INCLUDE ALL QUANTITIES, DETAIL DIMENSIONS, FIELD MEASUREMENTS, FABRICATION PROCESS, MEANS, METHODS, SEQUENCES AND PROCEDURES OF CONSTRUCTION, COORDINATION OF WORK WITH ALL TRADES AND PERFORMING ALL WORK IN A SAFE AND SATISFACTORY MANNER. THE REVIEW OF SHOP DRAWINGS DOES NOT IMPLY ANY CHANGE IN ANY OTHER CONSULTANTS' OR PROFESSIONALS' RESPONSIBILITY RELATED TO DESIGN OF SPECIFIC ITEMS AS OUTLINED BY THE SPECIFICATIONS (SUCH AS STRUCTURAL STEEL CONNECTIONS, STEEL JOISTS, PRECAST ELEMENTS, ETC.). AFTER REVIEW, THE DRAWINGS WILL BE STAMPED AND RETURNED TO SHOW ONE OF THE FOLLOWING:
- | | |
|---------------------|---|
| <u>NOT REVIEWED</u> | SHOWS WORK WHICH IS NOT WITHIN THE SCOPE OF STRUCTURAL CONSULTING SERVICES. |
| <u>REVIEWED</u> | NO DEVIATIONS FROM THE CONTRACT DOCUMENTS NOTED. |
| <u>NOTED</u> | WE HAVE MADE COMMENTS. TO BE REVIEWED/INCORPORATED. SUBMIT RECORD PRINT. |
| <u>RESUBMIT</u> | REVISE AND RESUBMIT FOR REVIEW. |

D. MATERIALS

1. PROVIDE ONLY NEW STRUCTURAL MATERIALS IN ACCORDANCE WITH THE REFERENCE STANDARDS AND THE FOLLOWING, UNLESS OTHERWISE NOTED.
- 1.1 STRUCTURAL STEEL:
- (a) STRUCTURAL WIDE FLANGE AND WELDED WIDE FLANGE SHAPES (W, WWF) TO CONFORM TO CAN/CSA-G40.20/G40.21 GRADE 350W.
- (b) ANGLES AND CHANNELS (L, C) AND PLATES TO CONFORM TO CAN/CSA-G40.20/G40.21 GRADE 300W.
- (c) HOLLOW STRUCTURAL SECTIONS (HSS) TO CONFORM TO ASTM A500 GRADE C.
- 1.2 PRIME PAINT: CONFORM TO CISC/CPMA STANDARD 2-75.
- 1.3 STRUCTURAL BOLTS, NUTS AND WASHERS: CONFORM TO ASTM A325M.
- 1.4 NON-SHRINK GROUT = COMPRESSIVE STRENGTH OF 35 MPa At 24 HOURS.
- 1.5 BLOCK: CONFORM TO CAN3-A165 SERIES, MINIMUM COMPRESSIVE STRENGTH = 15.0 MPa (MIN.) BASED ON NET AREA.
- 1.6 MORTAR: CONFORM TO CSA A179 TYPE S FOR LOADBEARING WALLS UNLESS NOTED.
- 1.7 MASONRY GROUT: CONFORM TO CSA A179, 15 MPa MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS, 250 mm (10") SLUMP, MAXIMUM AGGREGATE SIZE 10 MM (3/8")
- 1.8 SAWN LUMBER: SPRUCE-PINE-FIR (S-P-F), NO. 2 GRADE OR BETTER UNLESS NOTED ON DRAWINGS. CONFORM TO CSA-0141.
- 1.9 PLYWOOD: CONFORM TO CSA O121 (DOUGLAS FIR PLYWOOD).

EXECUTION

- | | |
|--|--|
| | <p>STRUCTURAL STEEL</p> <p>1.1. PAINT ALL STRUCTURAL STEEL TO REQUIREMENTS OF CISC/CPMA 2-75. TOUCH UP ALL FIELD WELDS.</p> <p>1.2. ALL STRUCTURAL STEEL EXPOSED TO WEATHER SHALL BE GALVANIZED IN ACCORDANCE WITH CSA G164.</p> <p>1.3. ALL WELDS SHALL CONFORM TO CSA STANDARD W59.</p> <p>1.4. ALL WELDS EXPOSED TO VIEW SHALL BE GROUND SMOOTH.</p> <p>1.5. ANY ORGANIZATION UNDERTAKING TO WELD UNDER THIS CONTRACT SHALL BE CERTIFIED BY THE CANADIAN WELDING BUREAU UNDER REQUIREMENTS OF DIVISION 1 OR DIVISION 2.1 OF W47.1.</p> <p>1.6. UNLESS A REINFORCED MASONRY OR CONCRETE LINTEL IS SHOWN, IN MASONRY WALLS OR MASONRY PARTITIONS PROVIDE LOOSE STEEL LINTELS IN ACCORDANCE WITH REQUIREMENTS OF DOCUMENTS OVER ALL DOORWAYS, OTHER OPENINGS, AND RECESSES, INCLUDING THOSE FOR MECHANICAL OR ELECTRICAL SERVICES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE THE LOCATION, SIZE AND NUMBER OF OPENINGS REQUIRED BY THE MECHANICAL AND ELECTRICAL CONSULTANT.</p> <p>1.7. DO NOT SPLICE STRUCTURAL STEEL SECTIONS WITHOUT PRIOR APPROVAL OF THE CONSULTANT. ALL SPLICES SHALL DEVELOP THE FULL CAPACITY OF THE SECTION AND ARE TO BE TESTED BY NON DESTRUCTIVE METHODS, BY AN INDEPENDENT INSPECTION AND TESTING COMPANY, AT THE CONTRACTOR'S EXPENSE.</p> <p>1.8. FOR TIMBER CONSTRUCTION TOP OF ALL STEEL BEAMS TO BE PRE-DRILLED TO ALLOW A 2" x 6" TIMBER NAILER TO BE INSTALLED. NAILER TO BE BOLTED WITH 1/2" DIA. BOLTS AT 4'-0" o/c, STAGGERED EACH SIDE.</p> <p>1.9. COMPLETELY FILL VOIDS BENEATH STEEL BASES ON CONCRETE WITH AN APPROVED NON-SHRINKING 36 MPa (5 ksi) GROUT</p> <p>1.10. SEE ARCHITECTURAL DRAWINGS FOR FIREPROOFING REQUIREMENTS. CONFIRM COMPATIBILITY OF FIREPROOFING MATERIAL WITH STEEL PAINT.</p> <p>2. MASONRY</p> <p>2.1. PROVIDE A MINIMUM LENGTH OF 200 mm (8") OF 100% SOLID MASONRY UNITS FOR BEARING OF STEEL, CONCRETE OR REINFORCED MASONRY LINTELS.</p> <p>2.2. SUPPLY AND PLACE REINFORCEMENT AND CONCRETE FOR REINFORCED MASONRY LINTELS IN ACCORDANCE WITH TYPICAL DETAILS SHOWN.</p> <p>2.3. FOR THE PURPOSE OF DETERMINING THE REQUIRED REINFORCING FOR LOAD-BEARING AND NON-LOAD BEARING MASONRY WALLS THE SEISMIC HAZARD INDEX IEFASA(0.2) = 0.19. REFER TO TYPICAL DETAILS FOR REINFORCING REQUIREMENTS.</p> <p>3. TIMBER FRAMING</p> <p>3.1. ALL FRAMING, BRIDGING, NAILING, PROTECTION, HARDWARE AND OTHER FRAMING DETAILS ARE TO BE IN ACCORDANCE WITH PART 9 OF THE ONTARIO BUILDING CODE, LATEST EDITION.</p> <p>3.2. EXTERIOR WALL SHEATHING TO BE 12 mm (1/2") EXTERIOR GRADE FIR PLYWOOD NAILED AT 150 mm (6") o/c ALONG EDGES AND 300 mm (12") o/c ON INTERMEDIATE FRAMING MEMBERS. SHEATHING PROVIDES LATERAL SUPPORT FOR FRAMING AND MUST BE NAILED TO EACH STUD.</p> <p>3.3. FLOOR SHEATHING TO BE 16 mm (5/8") T & G FIR PLYWOOD SUB FLOOR GLUED AND NAILED SECURELY TO ALL JOISTS.</p> <p>3.4. TIMBER PLANK DECKING IS TO BE LAID IN A [CONTROLLED RANDOM] [SIMPLE SPAN] [TWO SPAN CONTINUOUS] PATTERN.</p> <p>3.5. ROOF SHEATHING TO BE 12 mm (1/2") EXTERIOR GRADE FIR PLYWOOD NAILED AT 150 mm (6") o/c ALONG EDGES AND 300 mm (12") o/c ON INTERMEDIATE FRAMING MEMBERS. PROVIDE 3 mm (1/8") GAP BETWEEN SHEATHING PIECES.</p> <p>3.6. WIND LOADS SHALL BE IN ACCORDANCE WITH THE ONTARIO BUILDING CODE. PROVIDE FRAMING ANCHORS TO RESIST UPLIFT AT EACH END OF EACH ROOF JOIST. ANCHORS TO HAVE A WORKING CAPACITY OF 0.5 kN (100 lbs).</p> <p>3.7. UNLESS SPECIFICALLY NOTED OTHERWISE ON THE DRAWINGS, THE CONTRACTOR SHALL PROVIDE STANDARD SIMPSON STRONG TIE HARDWARE OR APPROVED EQUIVALENT FOR ALL JOIST HANGERS, BEAM HANGERS, BEAM SEATS, POST ANCHORS, ETC.</p> <p>3.8. MEMBERS SHALL BE ALIGNED LEVEL AND PLUMB, WITHIN A TOLERANCE OF 1 IN 500.</p> <p>3.9. MAKE ADEQUATE PROVISIONS FOR ERECTION STRESSES AND FOR SUFFICIENT TEMPORARY BRACING TO KEEP THE STRUCTURAL FRAME PLUMB AND IN TRUE ALIGNMENT UNTIL THE COMPLETION OF THE ENTIRE FRAMING INCLUDING INSTALLATION OF THE FLOOR AND WALL SHEATHING.</p> <p>3.10. FRAME AROUND ALL OPENINGS WITH DOUBLE HEADERS AND TRIMMERS NAILED TOGETHER WITH TWO ROWS OF 89 mm (3-1/2") SPIRAL NAILS AT 200 mm o/c (8" o/c) STAGGERED UNLESS NOTED OTHERWISE. DO NOT SPLICE MEMBERS BETWEEN SUPPORTS.</p> <p>3.11. FOR ALL BUILT UP BEAMS SUPPORTED ON TIMBER WALLS, SUPPORT BEAMS ON POSTS WITH AN EQUAL NUMBER OF LAMINATIONS UNLESS NOTED OTHERWISE.</p> <p>3.12. ALL BUILT UP BEAMS TO BE NAILED TOGETHER WITH TWO ROWS OF 89 mm (3-1/2") SPIRAL NAILS AT 200 mm (8") o/c. STAGER ROWS TOP AND BOTTOM. DO NOT SPLICE MEMBERS BETWEEN SUPPORTS.</p> <p>3.13. ALL BEAMS SUPPORTED ON TIMBER WALLS ARE TO BEAR ON BUILT UP POSTS OR BE CONNECTED TO OTHER BEAMS WITH METAL BEAM HANGERS. PRESSURE NAILING PLATES WILL NOT BE ACCEPTED.</p> <p>3.14. ALL BUILT UP POSTS ARE TO BE CONSTRUCTED CONTINUOUSLY TO THE FOUNDATION WITH TRANSFER BLOCKING AT EACH FLOOR FRAMING. POSTS ARE TO CONTINUE TO FOUNDATIONS EVEN IF SUPPORTED ON LOADBEARING STUD WALLS, UNLESS NOTED OTHERWISE ON THE DRAWINGS.</p> <p>3.15. BUILT UP POSTS OF 2 OR 3 PLY SHALL BE NAILED TOGETHER AT 150 mm (6") o/c STAGGERED UNLESS NOTED OTHERWISE.</p> <p>3.16. PROVIDE DOUBLE FLOOR JOISTS AT ALL NON-LOADBEARING AND LOADBEARING PARTITION WALLS SPANNING PARALLEL TO THE FLOOR FRAMING UNLESS OTHERWISE NOTED.</p> <p>3.17. PROVIDE SOLID BLOCKING, MATCHING JOIST MEMBER SIZE, UNDER ALL LOADBEARING WALLS OFFSET FROM THE SUPPORTS BELOW FOR FLOOR JOISTS SPANNING PERPENDICULAR TO THE WALL.</p> <p>3.18. PROVIDE SOLID BLOCKING BETWEEN JOISTS OVER SUPPORT AT ALL CANTILEVERED CONDITIONS.</p> <p>3.19. PROVIDE THE FOLLOWING HEADERS UNLESS NOTED OTHERWISE ON THE DRAWINGS:</p> <p>WINDOW & DOOR OPENING < 2,100 mm (7'-0" : 2 - 38x235 (2"x10") NO.2</p> <p>WINDOW & DOOR OPENING > 3,000 mm (10'-0" : 3 - 38x235 (2"x10") NO.2</p> |
|--|--|

- 3.20. PROVIDE 38x38 (2"x2") DIAGONAL CROSS BRIDGING AT MAXIMUM 2,100 mm (6'-11") c/c UNLESS NOTED OTHERWISE, FOR ALL SAWN JOIST LOCATIONS.
- 3.21. PROVIDE MINIMUM BEARING OF 38 mm (1 1/2") FOR ALL JOISTS.
- 3.22. PROVIDE MINIMUM BEARING OF 100 mm (4") FOR ALL BEAMS.
- 3.23. NO SAWN LUMBER SHALL BE NOTCHED OR DRILLED IN THE FIELD WITHOUT THE PERMISSION OF THE CONSULTANT.
- 3.24. WOOD IS NOT PERMITTED TO BEAR DIRECTLY ON MASONRY OR CONCRETE WITHOUT PROTECTION. PROVIDE EITHER PRESSURE TREATED WOOD OR A POLYETHYLENE SHEET BETWEEN THE WOOD AND MASONRY/CONCRETE.
- 3.25. ALL NAILERS TO BE ANCHORED WITH 12 mm (1/2") DIAMETER ANCHOR BOLTS x 300 mm (12") LONG AT 1,200 mm (4'-0") ON CENTRES. STAGGER ANCHOR BOLTS.
4. POST-INSTALLED ANCHORS
- 4.1. ANCHOR CAPACITY USED IN DESIGN SHALL BE BASED ON THE TECHNICAL DATA PUBLISHED BY HILTI OR SUCH OTHER METHOD AS APPROVED BY THE STRUCTURAL ENGINEER OF RECORD. SUBSTITUTION REQUESTS FOR ALTERNATE PRODUCTS MUST BE APPROVED IN WRITING BY THE STRUCTURAL ENGINEER OF RECORD PRIOR TO USE. CONTRACTOR SHALL PROVIDE CALCULATIONS DEMONSTRATING THAT THE SUBSTITUTED PRODUCT IS CAPABLE OF ACHIEVING THE PERFORMANCE VALUES OF THE SPECIFIED PRODUCT. SUBSTITUTIONS WILL BE EVALUATED FOR COMPLIANCE WITH THE RELEVANT BUILDING CODE FOR SEISMIC USES, LOAD RESISTANCE, INSTALLATION CATEGORY, AND AVAILABILITY OF COMPREHENSIVE INSTALLATION INSTRUCTIONS. ADHESIVE ANCHOR EVALUATION WILL ALSO CONSIDER CREEP, IN-SERVICE TEMPERATURE AND INSTALLATION TEMPERATURE.
- 4.2. INSTALL ANCHORS PER THE MANUFACTURER INSTRUCTIONS, AS INCLUDED IN THE ANCHOR PACKAGING.
- 4.3. OVERHEAD ADHESIVE ANCHORS MUST BE INSTALLED USING THE HILTI PROFI SYSTEM.
- 4.4. THE CONTRACTOR SHALL ARRANGE AN ANCHOR MANUFACTURER'S REPRESENTATIVE TO PROVIDE ONSITE INSTALLATION TRAINING FOR ALL OF THEIR ANCHORING PRODUCTS SPECIFIED. THE STRUCTURAL ENGINEER OF RECORD MUST RECEIVE DOCUMENTED CONFIRMATION THAT ALL OF THE CONTRACTOR'S PERSONNEL WHO INSTALL ANCHORS ARE TRAINED PRIOR TO THE COMMENCEMENT OF INSTALLING ANCHORS.
- 4.5. ANCHOR CAPACITY IS DEPENDANT UPON SPACING BETWEEN ADJACENT ANCHORS AND PROXIMITY OF ANCHORS TO EDGE OF CONCRETE. INSTALL ANCHORS IN ACCORDANCE WITH SPACING AND EDGE CLEARANCES INDICATED ON THE DRAWINGS.
- 4.6. EXISTING REINFORCING BARS IN THE CONCRETE STRUCTURE MAY CONFLICT WITH SPECIFIC ANCHOR LOCATIONS. UNLESS NOTED ON THE DRAWINGS THAT THE BARS CAN BE CUT, THE CONTRACTOR SHALL REVIEW THE EXISTING STRUCTURAL DRAWINGS AND SHALL UNDERTAKE TO LOCATE THE POSITION OF THE REINFORCING BARS AT THE LOCATIONS OF THE CONCRETE ANCHORS, BY HILTI FERROSCAN, HILTI PS 1000, GPR, X-RAY, CHIPPING OR OTHER MEANS.
5. ALTERATIONS AND/OR CONNECTIONS TO EXISTING STRUCTURE
- 5.1. INSPECT THE EXISTING BUILDING AND BECOME THOROUGHLY FAMILIAR WITH THE EXISTING CONDITIONS.
- 5.2. PRIOR TO PROCEEDING WITH THE WORK, DETERMINE THE EXACT FOUNDING ELEVATIONS OF EXISTING FOOTINGS ADJACENT TO THE NEW WORK. REPORT THESE FINDINGS TO THE CONSULTANT.
- 5.3. PRIOR TO FABRICATION OF STRUCTURAL STEEL, OPEN UP ALL AREAS WHERE CONNECTIONS ARE TO BE MADE TO EXISTING WORK AND TAKE FIELD MEASUREMENTS. MODIFY METHODS FOR CONNECTING TO SUIT SITE CONDITIONS FOUND AND TO THE APPROVAL OF THE CONSULTANT. CARRY OUT LOCAL REPAIRS TO THE EXISTING WORK AS NECESSARY AND AS DIRECTED BY THE CONSULTANT.
- 5.4. SHORE EXISTING WORK AS REQUIRED UNTIL ALL NEW WORK HAS BEEN COMPLETED AND REVIEWED BY THE CONSULTANT.
- 5.5. PROVIDE SLOTTED HOLES AND FRICTION TYPE BOLTED CONNECTIONS TO CONNECT NEW STEEL TO EXISTING WORK.
- 5.6. SHORE FLOORS AS REQUIRED TO SUPPORT CRANES, HOISTS AND OTHER CONSTRUCTION EQUIPMENT.
- 5.7. DO NOT CUT CONCRETE REINFORCEMENT UNLESS REVIEWED AND APPROVED BY THE CONSULTANT.
- 5.8. WHERE REQUIRED TO AVOID CUTTING EXISTING REINFORCEMENT, MODIFY THE LAYOUT OF NEW THROUGH BOLTS, EXPANSION ANCHORS AND OTHER ANCHORING DEVICES.
- 5.9. MAKE GOOD THE EXISTING WORK.
- 5.10. CLOSE OFF ALL OPENINGS IN WALLS LEFT BY REMOVAL OF EX DUCTWORK (SEE MECH DEMOLITION DWGS), USING LIKE MATERIAL TO THE SURROUNDING WALLS.
- 5.11. CLOSE OFF ALL OPENINGS IN ROOF LEFT BY REMOVAL OF EX DUCTWORK (SEE MECH DEMOLITION DWGS), USING LIKE MATERIAL TO THE SURROUNDING ROOF STRUCTURAL SYSTEM.

F. QUALITY CONTROL

- | | |
|-----|--|
| 1. | GENERAL |
| 1.1 | IMPLEMENT A SYSTEM OF QUALITY CONTROL TO ENSURE THAT THE MINIMUM STANDARDS SPECIFIED HEREIN ARE ATTAINED. |
| 1.2 | BRING TO THE ATTENTION OF THE CONSULTANT ANY DEFECTS IN THE WORK OR DEPARTURES FROM THE CONTRACT DOCUMENTS, WHICH MAY OCCUR DURING CONSTRUCTION. THE CONSULTANT WILL DECIDE UPON CORRECTIVE ACTION AND GIVE RECOMMENDATIONS IN WRITING. |
| 1.3 | THE CONSULTANT'S GENERAL REVIEW DURING CONSTRUCTION AND INSPECTION AND TESTING BY INDEPENDENT INSPECTION AND TESTING AGENCIES REPORTING TO THE CONSULTANT ARE BOTH UNDERTAKEN TO INFORM THE OWNER/CLIENT OF THE CONTRACTOR'S PERFORMANCE AND SHALL IN NO WAY AUGMENT THE CONTRACTOR'S QUALITY CONTROL OR RELIEVE THE CONTRACTOR OF CONTRACTUAL RESPONSIBILITY. |
| 2. | NOTIFICATION |
| 2.1 | PRIOR TO COMMENCING SIGNIFICANT SEGMENTS OF THE WORK, GIVE THE CONSULTANT AND INDEPENDENT INSPECTION AND TESTING COMPANIES APPROPRIATE NOTIFICATION (MINIMUM 24 HOURS) SO AS TO AFFORD THEM REASONABLE OPPORTUNITY TO REVIEW THE WORK. FAILURE TO MEET THIS REQUIREMENT MAY BE CAUSE FOR THE CONSULTANT TO CLASSIFY THE WORK AS DEFECTIVE. |

- | | |
|-----|---|
| 3. | INSPECTION AND TESTING |
| 3.1 | AN INDEPENDENT INSPECTION AND TESTING COMPANY SHALL MAKE INSPECTIONS OR PERFORM TESTS AS THE CONSULTANT DIRECTS. THE INDEPENDENT INSPECTION AND TESTING COMPANIES SHALL BE RESPONSIBLE ONLY TO THE CONSULTANT AND SHALL MAKE ONLY SUCH INSPECTIONS OR TESTS AS THE CONSULTANT MAY DIRECT. |
| 3.2 | THE FOLLOWING ITEMS REQUIRE TESTING AND/OR INSPECTION BY A CERTIFIED, INDEPENDENT INSPECTION AND TESTING COMPANY UNLESS OTHERWISE NOTED. THE TESTING FIRM SHALL SUBMIT COPIES OF ALL STRUCTURAL TESTING AND INSPECTION REPORTS TO THE CONSULTANT FOR REVIEW: |

ITEM	REQUIRED	COMMENTS
STRUCTURAL STEEL ERECTION	YES	REVIEW MEMBER SIZE, PLUMBNESS, BOLTED CONNECTIONS, ETC.
STRUCTURAL STEEL WELDING	YES	VISUALLY INSPECT ALL FIELD WELDING

4. DEFECTIVE MATERIALS AND WORK
- 4.1 WHERE EVIDENCE EXISTS THAT DEFECTIVE WORK HAS OCCURRED OR THAT WORK HAS BEEN CARRIED OUT INCORPORATING DEFECTIVE MATERIALS, THE CONSULTANT MAY HAVE TESTS, INSPECTIONS OR SURVEYS PERFORMED, ANALYTICAL CALCULATIONS OF STRUCTURAL STRENGTH MADE, AND THE LIKE, IN ORDER TO HELP DETERMINE WHETHER THE WORK MUST BE CORRECTED OR REPLACED. TESTS, INSPECTIONS OR SURVEYS OR CALCULATIONS CARRIED OUT UNDER THESE CIRCUMSTANCES WILL BE MADE AT THE CONTRACTOR'S EXPENSE, REGARDLESS OF THEIR RESULTS, WHICH MAY BE SUCH THAT, IN THE CONSULTANT'S OPINION, THE WORK MAY BE ACCEPTABLE.
- 4.2 ALL TESTING SHALL BE CONDUCTED IN ACCORDANCE WITH THE REQUIREMENTS OF THE 2012 BUILDING CODE (ONTARIO REGULATION 332/12, EXCEPT WHERE THIS WOULD, IN THE CONSULTANT'S OPINION, CAUSE UNDUE DELAY OR GIVE RESULTS NOT REPRESENTATIVE OF THE REJECTED MATERIAL IN PLACE. IN THIS CASE, THE TESTS SHALL BE CONDUCTED IN ACCORDANCE WITH THE STANDARDS GIVEN BY THE CONSULTANT.
- 4.3 MATERIALS OR WORK, WHICH FAIL TO MEET SPECIFIED REQUIREMENTS, MAY BE REJECTED BY THE CONSULTANT WHENEVER FOUND AT ANY TIME PRIOR TO FINAL ACCEPTANCE OF THE WORK REGARDLESS OF PREVIOUS INSPECTION. IF REJECTED, DEFECTIVE MATERIALS OR WORK SHALL BE PROMPTLY REMOVED AND REPLACED OR REPAIRED TO THE SATISFACTION OF THE CONSULTANT, AT NO EXPENSE TO THE OWNER.



310 Spadina Ave, Suite 100B
Toronto, Ontario, Canada M5T 2E8
T: 416 203 7600 F: 416 203 3342
lga-ap.com

NOTE: This drawing is the property of the architect and may not be reproduced or used without the expressed consent of the architect. The contractor shall be responsible for checking and verifying all levels and dimensions and shall report all discrepancies to the architect and obtain clarification prior to commencing work. Not for construction unless stamped by the architect and issued for such purpose.



375 University Ave., Suite 901
Toronto, ON M5G 2J5
416-599-(LINK) 5465
www.engineeringlink.ca
Project No. 21-1055-04

All reproduction & intellectual property rights reserved ©2024



ISSUE DATE

[illegible]

NO.	DATE	DESCRIPTION
-----	------	-------------

PROJECT:

MACGREGOR PUBLIC SCHOOL - PHASE 4

DRAWING TITLE

GENERAL NOTES

PROJECT NO:	21965	PROJECT NORTH:	
SCALE:	N/A		
DRAWN BY:	JRP/NAZ		
REVIEWED BY:	CN / PDS		

DRAWING NO:

S101