


9/7/2024 12:36:30 PM



ROOF FRAMING PLAN

SCALE: 3/32" = 1'-0"



1. TRUSS BEARING (TOP OF STEEL BEAMS) ELEVATION +14'-0" AFF, UNLESS NOTED.
2. ROOF SYSTEM: 1 1/2" STEEL ROOF DECK ON LGT GA METAL TRUSSES AT 4'-0" OC, BEARING ON STEEL BEAMS, UNLESS NOTED. SEE GENERAL NOTES FOR ROOF DECK ATTACHMENT PATTERN.
3. "4" INDICATES MOMENT CONNECTION. SEE TYPICAL DETAIL ON SHEET S1.04.
4. BEAM REACTIONS ARE INDICATED AT ENDS OF BEAMS AS "X" WHERE "X" IS THE MAGNITUDE OF THE ALLOWABLE LOAD (ASD) SHEAR REACTION IN KIPS. WHERE BEAM REACTION IS NOT SHOWN ON PLAN, DESIGN CONNECTION FOR SHEAR CONNECTIONS OF 15 KIPS.
5. IN ADDITION TO SHEAR REACTIONS, DESIGN CONNECTIONS TO COLUMNS WITH BEAM AXIAL FORCE OF 8 KIPS ALONG GRIDS 1, 3, 8, 10, B, C, J, AND N. PROVIDE DOUBLE ANGLE OR END PLATE CONNECTION TO COLUMNS.
6. PROVIDE LGT GA BENT PLATE 16GAx6"x6" AT ALL HIP AND VALLEYS. ATTACH TO EACH TRUSS SUPPORT USING 2#10 TEK SCREWS.
7. TRUSS LAYOUT SHOWN FOR GENERAL INTENT. EXACT LAYOUT OF LIGHTGAUGE STEEL TRUSSES TO BE DETERMINED BY THE TRUSS MANUFACTURER AND SUBMITTED TO THE STRUCTURAL ENGINEER.
8. PROVIDE HSS10x6x5/16 LOW. SEE SECTIONS FOR LOCATION.

ROOF FRAMING PLAN

TUSCALOOSA COUNTY DHR

Tuscaloosa, Alabama

GMC # ABHM220021

ISSUE DATE

BID SET 09/09/2024

sheet of

S2.02



2400 5th Avenue South, Suite 200

Birmingham, AL 35233

T 205.879.4462

GMCNETWORK.COM

GMC