







ROOF PLAN
1:100
STEEL DECK 1.5B, 22 JA, A-25 (LZC) TRIPLE SPAN, TYP UNO
TOP OF STEEL EL. 5486 mm

ROOF DECK DIAPHRAGM


- 1) GENERAL NOTES FOR DECK
- A) THE DECK IS REQUIRED TO ACT AS A LATERAL FORCE DISTRIBUTING DIAPHRAGM.
 - B) ☐ WELDED DECK
 - THE DECK MUST BE WELDED TO THE STRUCTURAL FRAMING SYSTEM WITH E60XX ELECTRODES.
 - ALL SPOT WELDS 19 mm ϕ TO BE DONE BY CANADIAN WELDING BUREAU QUALIFIED WELDER.
 - APPLY A SUITABLE PRIMER ON EACH BURNED TOPSIDE AREAS.
 - ☐ SCREWED DECK
 - THE STEEL DECK SHALL BE SCREWED TO STRUCTURAL SUPPORT WITH SCREWS TYPE TEK 5 #12-24x1 1/2".
 - ☒ NAILED
 - THE STEEL DECK SHALL BE NAILED TO STRUCTURAL SUPPORT WITH NAILS TYPE HLT-1 - X-HSN 24 - 3 mm s t s 10 mm - X-ANP19 L15-12.6 mm
 - THE ERECTOR IS RESPONSIBLE FOR THE FASTENING OF THE DECK TO THE STEEL STRUCTURE AND THE SELECTION OF THE FASTENER, THE TOOL, THE CARTRIDGE AS WELL AS THE POWER REGULATION OF THE TOOL IN ACCORDANCE WITH THE PRODUCT SPECIFICATIONS.
 - D) ERECTION SHALL BE IN ACCORDANCE WITH CSB1 10M-2013 PUBLICATIONS, AND ALL OTHER APPLICABLE STANDARDS.



2) FASTENER PATTERN AT SUPPORT



3) SIDE LAP FASTENING



4) PERIMETER FASTENING

- (2) A) ATTACH DECK TO PERIMETER MEMBER AT EACH RIB.
- (3) B) ATTACH DECK TO PERIMETER MEMBER @ 152 mm c/c.
- (4) C) ATTACH DECK TO LLH AND C200 @ 305 mm c/c.
- (5) D) ATTACH DECK TO ROOF OPENING FRAMES @ 152 mm c/c.

5) SHEAR CONNECTORS FASTENING

- A) PROVIDE ATTACHMENT BETWEEN DECK AND EACH SHEAR CONNECTOR WITH:
 - ☐ SPOT WELD 19 mm ϕ @ 152 mm c/c TYP. UN
 - ☐ SCREW TEK 5 #12-24x1 1/2" @ 152 mm c/c TYP. UN
 - ☐ HLT NAIL X-HSN 24 @ 152 mm c/c TYP. UN

LEGEND ROOF PLAN	
COL = Column	LLH = Long leg horizontal
EL = Elevation	LLV = Long leg vertical
J, X = Joist	RTU = Roof top unit
JG, X = Joist girder	
SS = Special steel	
TJ = Bottom chord tie, Tie joist	
[E] = Seismic axial load (kips) unfactored*	
[E] W E = Axial seismic load (kips) unfactored*	
W = Axial wind loads (kips) unfactored	
* = See "Design load notes" or as indicated on plans (around unit)	
<XX> = End reaction factored (kips)	
JOIST NOTES	
Depth shoe:	
JOIST	Less than 60'-0" = 4" height
	60'-0" & more = 5" height
	Maxon panels = 4" height
JOIST ORDER	Always = 7 1/2" height
CIC HOLES	Joist & joist girder
	See joist department
All joist and bridging will be bolted.	

REINFORCEMENTS AROUND ROOF OPENINGS	
Weight of the unit:	
- Less than 1000 lbs (450 kg) : L3x3x1/4 (L76x76x6.4) around unit and opening	
- Between 1000 lbs (450 kg) and 3000 lbs (1360 kg) : - 20x4.2 (C160x12) around unit - L3x3x1/4 (L76x76x6.4) opening	
- 3000 lbs (1360 kg) and more : C8x11.5 (C200x17) or as indicated on plans (around unit)	
- L3x3x1/4 (L76x76x6.4) opening	

REFER TO SHEET MX1000 FOR ALL DEMOLITION SCOPE AND RELATED REQUIREMENTS.

FOR PERMIT

B	JUNE120026	For Permit	A.D.	J.L.
A	MAY120026	60% Review Submission	A.D.	M.C.
REVISION	DATE	DESCRIPTION	BY	CHK

DRAWING	DESIGNED	PROJECT ENGINEER	SCALE
Stefan Gras	Imola Aranyosi	Martin Couture	AS INDICATED
CHECKED	CONSULTING ENGINEERS ARCHITECTS	DATE (yyyy/mm/dd)	
Arthur Dugay	GRAVITY ENGINEERING & NEGOTIC	2026/04/14	

CUSTOMER: CANADIAN TIRE CORPORATION LTD.



PROJECT
CTC 638
HUMBOLDT, SASKATCHEWAN

ROOF PLAN & DETAILS			
CONTRACT NUMBER	DRAWING NUMBER	DIVISION	REVISION
P0000-000	Mx401		B
260890			