






ROOF PLAN
1:100
STEEL DECK 1.5B, 22 JA, A-25 (LZC) TRIPLE SPAN, TYP UNO
TOP OF STEEL EL. 5486 mm


ROOF DECK DIAPHRAGM

1) GENERAL NOTES FOR DECK

- A) THE DECK IS REQUIRED TO ACT AS A LATERAL FORCE DISTRIBUTING DIAPHRAGM.
- B) ☐ WELDED DECK
 - THE DECK MUST BE WELDED TO THE STRUCTURAL FRAMING SYSTEM WITH E60XX ELECTRODES.
 - ALL SPOT WELDS 19 mm ϕ TO BE DONE BY CANADIAN WELDING BUREAU QUALIFIED WELDER.
 - APPLY A SUITABLE PRIMER ON EACH BURNED TOPSIDE AREAS.
- ☐ SCREWED DECK
 - THE STEEL DECK SHALL BE SCREWED TO STRUCTURAL SUPPORT WITH SCREWS TYPE TEK 5 #12-24x1 1/2".
- ☒ NAILED
 - THE STEEL DECK SHALL BE NAILED TO STRUCTURAL SUPPORT WITH NAILS TYPE HLT-1 - X-HSN 24 - 3 mm s t s 10 mm - X-ANP19 L15-12.6 mm
 - THE ERECTOR IS RESPONSIBLE FOR THE FASTENING OF THE DECK TO THE STEEL STRUCTURE AND THE SELECTION OF THE FASTENER, THE TOOL, THE CARTRIDGE AS WELL AS THE POWER REGULATION OF THE TOOL IN ACCORDANCE WITH THE PRODUCT SPECIFICATIONS.
- D) ERECTION SHALL BE IN ACCORDANCE WITH CSB1 10M-2013 PUBLICATIONS, AND ALL OTHER APPLICABLE STANDARDS.



1) 2) FASTENER PATTERN AT SUPPORT



3) SIDE LAP FASTENING

SIDE LAP SHALL BE SCREW:

- ☐ SCREW TEK 2 #10 - 16 x 1 1/2"

- ☒ HLT S-SLC 01 M HHW (22 ga. 20 ga. & 18 ga.)
- ☐ HLT S-SLC 02 M HHW (16 ga.)

- ☒ @ 152 mm c/c
- ☒ @ 305 mm c/c
- ☒ @ 610 mm c/c

- ☐ @ 152 mm c/c
- ☐ @ 305 mm c/c
- ☐ @ 610 mm c/c

- ☒ @ 152 mm c/c
- ☒ @ 305 mm c/c
- ☒ @ 610 mm c/c

4) PERIMETER FASTENING

- (2) A) ATTACH DECK TO PERIMETER MEMBER AT EACH RIB.
- (3) B) ATTACH DECK TO PERIMETER MEMBER @ 152 mm c/c.
- (4) C) ATTACH DECK TO LLH AND C200 @ 305 mm c/c.
- (5) D) ATTACH DECK TO ROOF OPENING FRAMES @ 152 mm c/c.

5) SHEAR CONNECTORS FASTENING

- A) PROVIDE ATTACHMENT BETWEEN DECK AND EACH SHEAR CONNECTOR WITH:

- ☐ SPOT WELD 19 mm ϕ @ 152 mm c/c TYP. UN
- ☐ SCREW TEK 5 #12-24x1 1/2" @ 152 mm c/c TYP. UN
- ☒ HLT NAIL X-HSN 24 @ 152 mm c/c TYP. UN

All joist and bridging will be bolted.

REFER TO SHEET MX1000 FOR ALL DEMOLITION SCOPE AND RELATED REQUIREMENTS.

LEGEND ROOF PLAN

- COL = Column
- EL = Elevation
- J, X = Joist
- JG, X = Joist girder
- SS = Special steel
- TJ = Bottom chord tie, Tie joist
- [E] = Seismic axial load (kips) unfactored*
- [E] W E = Axial seismic load (kips) unfactored*
- W = Axial wind loads (kips) unfactored
- * = See "Design load notes" for seismic data, connections
- <XX> = End reaction factored (kips)

- LLH = Long leg horizontal
- LLV = Long leg vertical
- RTU = Roof top unit

JOIST NOTES

- JOIST : Less than 60'-0" = 4" height
- JOIST : 60'-0" & more = 5" height
- MAJOR PANELS : Less than 4" height
- JOIST ORDER : Always = 7 1/2" height
- CIC HOLES : Joist & joist girder
- See joist department

All joist and bridging will be bolted.

REFER TO SHEET MX1000 FOR ALL DEMOLITION SCOPE AND RELATED REQUIREMENTS.

REINFORCEMENTS AROUND ROOF OPENINGS

Weight of the unit :

- Less than 1000 lbs (450 kg) : L3x3x1/4 (L76x76x6.4) around unit and opening
- Between 1000 lbs (450 kg) and 3000 lbs (1360 kg) : L3x3x1/4 (L76x76x6.4) around unit
- 3000 lbs (1360 kg) and more : C8x11.5 (C200x17) or as indicated on plans (around unit)
- L3x3x1/4 (L76x76x6.4) opening

* = See "Design load notes" for seismic data, connections

<XX> = End reaction factored (kips)

REFER TO SHEET MX1000 FOR ALL DEMOLITION SCOPE AND RELATED REQUIREMENTS.

REFER TO SHEET MX1000 FOR ALL DEMOLITION SCOPE AND RELATED REQUIREMENTS.

REFER TO SHEET MX1000 FOR ALL DEMOLITION SCOPE AND RELATED REQUIREMENTS.

REFER TO SHEET MX1000 FOR ALL DEMOLITION SCOPE AND RELATED REQUIREMENTS.

REFER TO SHEET MX1000 FOR ALL DEMOLITION SCOPE AND RELATED REQUIREMENTS.

FOR PERMIT

B	JUNE12/2026	For Permit	A.D.	J.L.
A	MAY12/2026	60% Review Submission	A.D.	M.C.
REVISION	DATE	DESCRIPTION	BY	CHK

PROJECT MANAGER				
DRAWING				
DESIGNED	Imola Aranyosi	PROJECT ENGINEER	SCALE	AS INDICATED
CHECKED	Arthur Dugay	CONSULTING ENGINEERS ARCHITECTS	DATE (YYYYMMDD)	2026/04/14

CUSTOMER	CANADIAN TIRE CORPORATION LTD.
PROFESSIONAL SEAL	
PROFESSIONAL ENGINEER	

PROJECT	
CTC 638	
HUMBOLDT, SASKATCHEWAN	

11505, 1re Avenue, bureau 500, Saint-Georges Beauce

Quebec, Canada, G5Y 7G3

Phone : (418) 228-8031

Toll free : (877) 499-6049

www.canam.com

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14

2026/04/14