

9/7/2023 9:21:59 AM Autodesk Docs://1230237 Port Wentworth Fire Station/1230237_Port Wentworth FS_MEPE_v23.rvt

1	2	3	4	5											
LUMINAIRE SCHEDULE											SHEET NOTES 1. REFER TO SHEETS E-001 & E-002 FOR ELECTRICAL GENERAL NOTES, ABBREVIATIONS & LEGEND.				
FIXTURE	DESCRIPTION	LAMP	LUMENS	CRI	CCT	VOLTAGE	WATTAGE	MOUNTING	MANUFACTURER (BASIS OF DESIGN)	NOTES					
A	4 x 4 LED TROFFER	LED	4,800	82	5000K	277 V	39 W	CEILING GRID	LITHONIA LIGHTING 2FSL4 48L GZ10 LP850	1,2					
AE	4 x 4 LED TROFFER W/EMERGENCY CONNECTION	LED	4,800	82	5000K	277 V	39 W	CEILING GRID	LITHONIA LIGHTING 2FSL2 48L GZ10 LP850 BGTD	1,2,3					
B	2 x 2 LED TROFFER	LED	4,800	82	5000K	277 V	41 W	CEILING GRID	LITHONIA LIGHTING 2FSL2 48L GZ10 LP850	1,2					
BE	2 x 2 LED TROFFER W/EMERGENCY CONNECTION	LED	4,800	82	5000K	277 V	41 W	CEILING GRID	LITHONIA LIGHTING 2FSL2 48L GZ10 LP850 BGTD	1,2,3					
C1E	LED SUSPENDED 1 x 4 STRIP W/EMERGENCY CONNECTION	LED	6,000	80	5000K	277 V	45 W	SUSPENDED	LITHONIA LIGHTING UFIT L48 6000LM SEF MVOLT GZ10 80CRI WH	1,2,3					
C2	LED SUSPENDED 1 x 4 STRIP	LED	5,000	80	5000K	277 V	51 W	SUSPENDED	LITHONIA LIGHTING L48 5000LM SEF WDL MVOLT EDAB TUWH PROR NLT 80CRI WH	1,2					
C2E	DIRECT/INDIRECT PENDANT W/BLACK FINISH W/BATTERY BACKUP	LED	4,000	80	5000K	277 V	51 W	SUSPENDED	LITHONIA LIGHTING L48 5000LM SEF WDL MVOLT EDAB TUWH PROR NLT 80CRI WH	1,2,3					
CF	CEILING FAN WITH LIGHT KIT.	LED BULBS				120 V	60 W	CEILING		1,2					
DE	LED SUSPENDED 1 x 4 STRIP W/EMERGENCY CONNECTION	LED	4,000	82	5000K	277 V	40 W	SUSPENDED	LITHONIA LITHING WL4 40L GZ10 LP850	1,2,3					
E1	LED 1 x 4 WALL MOUNTED STRIP WITH INTEGRAL OCCUPANCY SENSOR	LED	4,800	82	5000K	277 V	40 W	WALL	LITHONIA LIGHTING BLWP4 48L ADP GZ10 LP850 MSD7ADCX DIM50	1,2,5					
E2	LED 1 x 4 WALL MOUNTED WET LOCATION RATED	LED	5,000	80	5000K	277 V	42 W	WALL	LITHONIA LIGHTING CVST L48 AL03 SWW3 80CRI	1,2,4					
EF1	6" SQUARE RECESSED LED DOWNLIGHT W/EMERGENCY CONNECTION	LED	4,000	80	5000K	277 V	39 W	RECESSED	GOTHAM EVO6SQ 50/40 AR LSS MVOLT GZ10 BGTD	1,2,3					
F1	6" SQUARE RECESSED LED DOWNLIGHT	LED	4,000	80	5000K	277 V	39 W	RECESSED	GOTHAM EVO6SQ 50/40 AR LSS MVOLT GZ10	1,2,3					
F2	6" SQUARE RECESSED LED DOWNLIGHT DAMP LOCATION RATED	LED	2,500	80	5000K	277 V	25 W	RECESSED	GOTHAM EVO6SQSH 50/25 DFR SMO MVOLT	1,2,3,4					
HB	LED HIGH BAY	LED	15,000	80	5000K	277 V	137 W	SUSPENDED	LITHONIA LIGHTING IBHST 15000LM SD080 MD MVOLT OZ10 50K 80CRI WH	1,2					
HBE	LED HIGH BAY W/EMERENCY CONNECTION	LED	15,000	80	5000K	277 V	137 W	SUSPENDED	LITHONIA LIGHTING IBHST 15000LM SD080 MD MVOLT OZ10 50K 80CRI WH BGTD	1,2,3					
ST	LED WALL MOUNT 1 x 4 STRIP	LED	2,200	82	5000K	277 V	21 W	WALL MOUNT 8' AFF	LITHONIA LIGHTING WL2 22L GZ10 MSD7 LP850	1,2,3,5					
WP	LED WALL PACK	LED	6,500		5000K	277 V	51 W	WALL	LITHONIA LIGHTING ARC2 LED P5 50K MVOLT PE DBLXD	1					
WS	EXTERIOR LED WALL SCONCE - WET LOCATION RATED	LED		80	4000K	277 V	14 W	WALL	LITHONIA LIGHTING OLLWU LED P1 40K MVOLT DDB	1					
X2	LED EXIT SIGN	LED				277 V	2 W	WALL/CEILING	EVENLITE SOVII R - - - -	1,2,3					
NOTES: 1. DESIGN BASIS SHOWN FOR REFERENCE ONLY. FIXTURES OF EQUAL QUALITY AND PERFORMANCE ARE ACCEPTABLE. ALL FIXTURES MUST BE EQUAL IN MATERIAL, QUALITY, WARRANTY, PHOTOMETRIC, SIZE AND FINISH. 2. VERIFY CEILING TYPES WITH ARCHITECTURAL DRAWINGS PRIOR TO ORDERING. 3. WIRE EXIT SIGNS AND EMERGENCY LUMINAIRES AHEAD OF ALL LOCAL SWITCHING. 4. LUMINAIRES TO BE UL LISTED FOR WET LOCATIONS. 5. LUMINAIRE PROVIDED WITH INTEGRAL OCCUPANCY SENSOR. WHEN UNOCCUPIED, LUMINAIRE TO DIM TO 50%.															
LUMINAIRE CONTROL SCHEDULE															
SPACE TYPE	ROOM NUMBER	MANUAL ON	MANUAL OFF	LOW-VOLTAGE DIMMING SYSTEM	LINE VOLTAGE DIMMING SWITCH	OCCUPANCY SENSOR ON	OCCUPANCY SENSOR OFF	VACANCY SENSOR OFF	AUTO BI-LEVEL CONTROL	ASTRONOMICAL TIME CLOCK		ASTRONOMICAL TC WITH PHOTOCELL CONTROL	INTEGRAL MOTION CONTROL	DAYLIGHT DIMMING CONTROL	CONTROLS NARRATIVE
BUNK		X	X												PROVIDE MANUAL ON/OFF SWITCH(ES) AT EACH ROOM ENTRY. NO OCCUPANCY SENSORS PERMITTED.
STORAGE						X	X								PROVIDE ON/OFF OCCUPANCY CONTROL WITH LOCAL OVERRIDE SWITCH.
ELECTRICAL		X	X												PROVIDE ON/OFF OCCUPANCY CONTROL.
CORRIDOR						X	X							PROVIDE ON/OFF OCCUPANCY CONTROL.	
EXERCISE						X	X							PROVIDE VACANCY OFF CEILING/WALL MOUNTED SENSOR(S) WITH LOCAL OVERRIDE SWITCH.	
LAUNDRY						X	X							PROVIDE VACANCY OFF CEILING/WALL MOUNTED SENSOR(S) WITH LOCAL OVERRIDE SWITCH.	
RESTROOMS / LOCKERROOMS						X	X							PROVIDE STAIRWELL LUMINAIRE WITH INTEGRAL OCCUPANCY SENSOR CONTROL TO FULL OUTPUT UPON SENSING OCCUPANCY. SET INTEGRAL DIMMING DRIVER TO 20% LIGHT OUTPUT SETTING AFTER 20 MINUTES OF VACANCY.	
IT/ COMM ROOMS						X	X							PROVIDE MANUAL ON/OFF SWITCH(ES) AT EACH ROOM ENTRY. NO OCCUPANCY SENSORS PERMITTED.	
MECHANICAL		X	X											PROVIDE VACANCY OFF CEILING/WALL MOUNTED SENSOR(S) WITH LOCAL OVERRIDE SWITCH.	
STAIR						X	X							PROVIDE VACANCY OFF WALL MOUNTED SENSOR(S) WITH LOCAL OVERRIDE SWITCH.	
LOBBY						X	X							PROVIDE VACANCY OFF CEILING/WALL MOUNTED SENSOR(S) WITH LOCAL OVERRIDE SWITCHES.	
TRAINING						X	X							PROVIDE ON/OFF OCCUPANCY CONTROL WITH LOCAL OVERRIDE SWITCH FOR RESTROOM AND LOCKER AREAS. PROVIDE VACANCY OFF WALL MOUNTED SENSOR WITH LOCAL OVERRIDE SWITCH FOR SHOWER AREAS.	
CHIEF		X						X						PROVIDE LOW-VOLTAGE VACANCY OFF - MANUAL ON CEILING MOUNTED SENSOR(S) WITH LOCAL OVERRIDE LOW-VOLTAGE DIMMING CONTROL SWITCH.	
OFFICE		X						X						PROVIDE LOW-VOLTAGE VACANCY OFF - MANUAL ON CEILING MOUNTED SENSOR(S) WITH LOCAL OVERRIDE LOW-VOLTAGE DIMMING CONTROL SWITCHES.	
JANITOR						X	X							PROVIDE LIGHTING CONTACTOR FOR EXTERIOR FIXTURES WITH ASTRONOMICAL TIME CLOCK.	
WASH						X	X							PROVIDE LIGHTING CONTACTOR WITH TIME CLOCK SET ON AT 5 AM, OFF AT 11 PM.	
ADMIN						X	X								
GEAR TURN OUT						X	X								
DECOM						X	X								
RECORDS						X	X								
RISER		X	X												
REC ROOM						X	X								
EXTERIOR										X					
100% DESIGN SUBMITTAL - NOT FOR CONSTRUCTION															