

LUMINAIRE SCHEDULE

FIXTURE	DESCRIPTION	LAMP	LUMENS	CRI	CCT	VOLTAGE	WATTAGE	MOUNTING	MANUFACTURER (BASIS OF DESIGN)	NOTES
A	4 x 4 LED TROFFER	LED	4,800	82	5000K	277 V	39 W	CEILING GRID	LITHONIA LIGHTING 2FSL4 48L GZ10 LP850	1,2
AE	4 x 4 LED TROFFER W/EMERGENCY CONNECTION	LED	4,800	82	5000K	277 V	39 W	CEILING GRID	LITHONIA LIGHTING 2FSL2 48L GZ10 LP850 BGTD	1,2,3
B	2 x 2 LED TROFFER	LED	4,800	82	5000K	277 V	41 W	CEILING GRID	LITHONIA LIGHTING 2FSL2 48L GZ10 LP850	1,2
BE	2 x 2 LED TROFFER W/EMERGENCY CONNECTION	LED	4,800	82	5000K	277 V	41 W	CEILING GRID	LITHONIA LIGHTING 2FSL2 48L GZ10 LP850 BGTD	1,2,3
C1E	LED SUSPENDED 1 x 4 STRIP W/EMERGENCY CONNECTION	LED	6,000	80	5000K	277 V	45 W	SUSPENDED	LITHONIA LIGHTING UFIT L48 6000LM SEF MVOLT GZ10 80CRI WH	1,2,3
C2	LED SUSPENDED 1 x 4 STRIP	LED	5,000	80	5000K	277 V	51 W	SUSPENDED	LITHONIA LIGHTING L48 5000LM SEF WDL MVOLT EDAB TUWH PROR NLT 80CRI WH	1,2
C2E	DIRECT/INDIRECT PENDANT W/BLACK FINISH W/BATTERY BACKUP	LED	4,000	80	5000K	277 V	51 W	SUSPENDED	LITHONIA LIGHTING L48 5000LM SEF WDL MVOLT EDAB TUWH PROR NLT 80CRI WH	1,2,3
CF	CEILING FAN WITH LIGHT KIT.	LED BULBS				120 V	60 W	CEILING		1,2
DE	LED SUSPENDED 1 x 4 STRIP W/EMERGENCY CONNECTION	LED	4,000	82	5000K	277 V	40 W	SUSPENDED	LITHONIA LITHING WL4 40L GZ10 LP850	1,2,3
E1	LED 1 x 4 WALL MOUNTED STRIP WITH INTEGRAL OCCUPANCY SENSOR	LED	4,800	82	5000K	277 V	40 W	WALL	LITHONIA LIGHTING BLWP4 48L ADP GZ10 LP850 MSD7ADXC DIM50	1,2,5
E2	LED 1 x 4 WALL MOUNTED WET LOCATION RATED	LED	5,000	80	5000K	277 V	42 W	WALL	LITHONIA LIGHTING CVST L48 AL03 SWW3 80CRI	1,2,4
EF1	6" SQUARE RECESSED LED DOWNLIGHT W/EMERGENCY CONNECTION	LED	4,000	80	5000K	277 V	39 W	RECESSED	GOTHAM EVO6SQ 50/40 AR LSS MVOLT GZ10 BGTD	1,2,3
F1	6" SQUARE RECESSED LED DOWNLIGHT	LED	4,000	80	5000K	277 V	39 W	RECESSED	GOTHAM EVO6SQ 50/40 AR LSS MVOLT GZ10	1,2,3
F2	6" SQUARE RECESSED LED DOWNLIGHT DAMP LOCATION RATED	LED	2,500	80	5000K	277 V	25 W	RECESSED	GOTHAM EVO6SQSH 50/25 DFR SMO MVOLT	1,2,3,4
HB	LED HIGH BAY	LED	15,000	80	5000K	277 V	137 W	SUSPENDED	LITHONIA LIGHTING IBHST 15000LM SD080 MD MVOLT OZ10 50K 80CRI WH	1,2
HBE	LED HIGH BAY W/EMERGENCY CONNECTION	LED	15,000	80	5000K	277 V	137 W	SUSPENDED	LITHONIA LIGHTING IBHST 15000LM SD080 MD MVOLT OZ10 50K 80CRI WH BGTD	1,2,3
ST	LED WALL MOUNT 1 x 4 STRIP	LED	2,200	82	5000K	277 V	21 W	WALL MOUNT 8' AFF	LITHONIA LIGHTING WL2 22L GZ10 MSD7 LP850	1,2,3,5
WP	LED WALL PACK	LED	6,500		5000K	277 V	51 W	WALL	LITHONIA LIGHTING ARC2 LED P5 50K MVOLT PE DBLXD	1
WS	EXTERIOR LED WALL SCONCE - WET LOCATION RATED	LED		80	4000K	277 V	14 W	WALL	LITHONIA LIGHTING OLLWU LED P1 40K MVOLT DDB	1
X2	LED EXIT SIGN	LED				277 V	2 W	WALL/CEILING	EVENLITE SOVII R - - - -	1,2,3

SHEET NOTES

1. REFER TO SHEETS E-001 & E-002 FOR ELECTRICAL GENERAL NOTES, ABBREVIATIONS & LEGEND.

LUMINAIRE CONTROL SCHEDULE

SPACE TYPE	ROOM NUMBER	MANUAL ON	MANUAL OFF	LOW-VOLTAGE DIMMING SYSTEM	LINE VOLTAGE DIMMING SWITCH	OCCUPANCY SENSOR ON	OCCUPANCY SENSOR OFF	VACANCY SENSOR OFF	AUTO BI-LEVEL CONTROL	ASTRONOMICAL TIME CLOCK	ASTRONOMICAL TC WITH PHOTOCELL CONTROL	INTEGRAL MOTION CONTROL	DAYLIGHT DIMMING CONTROL	CONTROLS NARRATIVE
BUNK		X	X											PROVIDE MANUAL ON/OFF SWITCH(ES) AT EACH ROOM ENTRY. NO OCCUPANCY SENSORS PERMITTED.
STORAGE						X	X							PROVIDE ON/OFF OCCUPANCY CONTROL WITH LOCAL OVERRIDE SWITCH.
ELECTRICAL		X	X											PROVIDE ON/OFF OCCUPANCY CONTROL.
CORRIDOR						X	X							PROVIDE ON/OFF OCCUPANCY CONTROL.
EXERCISE						X	X							PROVIDE VACANCY OFF CEILING/WALL MOUNTED SENSOR(S) WITH LOCAL OVERRIDE SWITCH.
LAUNDRY						X	X							PROVIDE VACANCY OFF CEILING/WALL MOUNTED SENSOR(S) WITH LOCAL OVERRIDE SWITCH.
RESTROOMS / LOCKERROOMS						X	X							PROVIDE STAIRWELL LUMINAIRE WITH INTEGRAL OCCUPANCY SENSOR CONTROL TO FULL OUTPUT UPON SENSING OCCUPANCY. SET INTEGRAL DIMMING DRIVER TO 20% LIGHT OUTPUT SETTING AFTER 20 MINUTES OF VACANCY.
IT/ COMM ROOMS						X	X							PROVIDE MANUAL ON/OFF SWITCH(ES) AT EACH ROOM ENTRY. NO OCCUPANCY SENSORS PERMITTED.
MECHANICAL		X	X											PROVIDE VACANCY OFF CEILING/WALL MOUNTED SENSOR(S) WITH LOCAL OVERRIDE SWITCH.
STAIR						X	X							PROVIDE VACANCY OFF WALL MOUNTED SENSOR(S) WITH LOCAL OVERRIDE SWITCH.
LOBBY						X	X							PROVIDE VACANCY OFF CEILING/WALL MOUNTED SENSOR(S) WITH LOCAL OVERRIDE SWITCHES.
TRAINING						X	X							PROVIDE ON/OFF OCCUPANCY CONTROL WITH LOCAL OVERRIDE SWITCH FOR RESTROOM AND LOCKER AREAS. PROVIDE VACANCY OFF WALL MOUNTED SENSOR WITH LOCAL OVERRIDE SWITCH FOR SHOWER AREAS.
CHIEF		X						X						PROVIDE LOW-VOLTAGE VACANCY OFF - MANUAL ON CEILING MOUNTED SENSOR(S) WITH LOCAL OVERRIDE LOW-VOLTAGE DIMMING CONTROL SWITCH.
OFFICE		X						X						PROVIDE LOW-VOLTAGE VACANCY OFF - MANUAL ON CEILING MOUNTED SENSOR(S) WITH LOCAL OVERRIDE LOW-VOLTAGE DIMMING CONTROL SWITCHES.
JANITOR						X	X							PROVIDE LIGHTING CONTACTOR FOR EXTERIOR FIXTURES WITH ASTRONOMICAL TIME CLOCK.
WASH						X	X							PROVIDE LIGHTING CONTACTOR WITH TIME CLOCK SET ON AT 5 AM, OFF AT 11 PM.
ADMIN						X	X							
GEAR TURN OUT						X	X							
DECOM						X	X							
RECORDS						X	X							
RISER		X	X											
REC ROOM						X	X							
EXTERIOR											X			

3500 Parkway Lane
Suite 500
Peachtree Corners
Georgia 30092

Copyright © 2023 by Pond & Company. All rights reserved. No copying or duplication of these documents is allowed without the expressed written agreement of Pond & Company.

EOR/AOR SEAL

100% DESIGN
SUBMITTAL - NOT FOR
CONSTRUCTION

CLIENT INFORMATION

CITY OF PORT
WENTWORTH

PROJECT NAME

PORT
WENTWORTH
FIRESTATION



DRAWING ISSUE

DATE _____

DESCRIPTION

MARK

DESIGNED BY: AS
DRAWN BY: AS
CHECKED BY: NN
SUBMITTED BY: CL
DATE: 9/08/2023
PROJECT #: 1230237

SHEET TITLE

LUMINAIRE SCHEDULE

SHEET NUMBER

E-611

ORIGINAL SHEET SIZE
22" X 34"

100% DESIGN SUBMITTAL - NOT FOR CONSTRUCTION